



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

259744

TICKET NUMBER 40019
LOCATION Cole, KS
FOREMAN Kelly Gebel

**FIELD TICKET & TREATMENT REPORT
CEMENT**

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|-----------------|------------|---------------------------|----------|----------|-------|--------|
| 6-18-13 | K16 | B3B Forms 1-194 | 19 | 115 | 44W | Kitsap |
| CUSTOMER | | Kirkpatrick Oil Co. Inc. | | | | |
| MAILING ADDRESS | | 106 South Main Po: Box 86 | | | | |
| CITY | | STATE | ZIP CODE | | | |
| Hennessey | | OK | 73742 | | | |
| JOB TYPE | | Surface | | | | |

| | | | |
|--|--------------------------|-----------------------|---------------------------------------|
| JOB TYPE <u>Surface</u> | HOLE SIZE <u>12 1/4"</u> | HOLE DEPTH <u>383</u> | CASING SIZE & WEIGHT <u>7 5/8-36#</u> |
| CASING DEPTH <u>328'</u> | DRILL PIPE _____ | TUBING _____ | OTHER _____ |
| SLURRY WEIGHT <u>148</u> | SLURRY VOL _____ | WATER gal/sk _____ | CEMENT LEFT In CASING <u>42'</u> |
| DISPLACEMENT <u>26 bbl</u> | DISPLACEMENT PSI _____ | MIX PSI _____ | RATE _____ |
| REMARKS: <u>safety meeting, rigged up on well, pumped rabbit water mixed w/ 200 sacks cement 3000cc 200 gal, released plug & displaced w/ 26 bbl water, shut in, washed out pump & lines, rigged down.</u> | | | |

Cement did circulate

Approx 16 bbl topst

[illegible]

Ravn 3737

AUTHORIZATION

TITLE

DATE 6-18-13

acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



FIELD TICKET & TREATMENT REPORT

TICKET NUMBER 37975
LOCATION Oakley, Ks
FOREMAN Walt Dinkel
ORT Miles Shaw

CEMENT

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY |
|---|-------------|--------------------|-----------------|--------------------------|---------|------------|
| 7-14-13 | K16 | B+B Farms 1-194 | 19 | 11S | 44W | Kit Carson |
| CUSTOMER Kirk Patrick Oil | | | Burlington | | | |
| MAILING ADDRESS 106 South main P.O. Box 86 | | | South to Road 6 | | | |
| CITY Hennessey | STATE OK | ZIP CODE 73742 | 6 W | | | |
| | | | 25 | | | |
| | | | 1/4 W-35 | | | |
| | | | TRUCK # | DRIVER | TRUCK # | DRIVER |
| | | | 456-T118 | Dane | | |
| | | | 528-T127 | Tim Wareham | | |
| | | | | Daniel Darrow Ride along | | |

| | | | |
|---|------------------------|-------------------------|-------------------------------------|
| JOB TYPE <u>Intermediate</u> | HOLE SIZE <u>8 3/4</u> | HOLE DEPTH <u>5964</u> | CASING SIZE & WEIGHT <u>7" - 26</u> |
| CASING DEPTH <u>13.8</u> ^{strings} | DRILL PIPE | TUBING | OTHER <u>DY D 3630'</u> |
| SLURRY WEIGHT <u>14.2</u> | SLURRY VOL | WATER gal/sk <u>6.3</u> | CEMENT LEFT in CASING <u>42.35</u> |
| DISPLACEMENT <u>874</u> , <u>138M</u> | DISPLACEMENT PSI | MIX PSI | RATE <u>7-8 BPM</u> |

REMARKS: Safety meeting, rig up on HWD #4, rig up to casing, ~~new~~ Pump
10 BBL Water spacer, mixed 200 SKS OWC, 5# Kokesal, Clear Pump + Lines
release Plug + Displaced 90 BBL H₂O + 106 BBL Mud, casing locked up @ 3000^{psi}
release Pressure, Drop opening tool, Open DY Tool, Circ. 6 Hrs,
mix 225 SKS Class C OWC, 5#, release Plug + Displace 140 BBL H₂O
@ 500^{psi}, Landed Plug + Shut Tool @ 1500^{psi}, release Pressure, Hold

Thank You
Walt-Miles & Crew

[illegible]

Ravin 3737

AUTHORIZATION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.