



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

TICKET NUMBER 38053
LOCATION Oakley, KS
FOREMAN Kelly Gabel
Walt Pinkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-2-13	5659	APC Baughman unit	35	165	452	Cherokee
CUSTOMER		MAILING ADDRESS	CITY	STATE	ZIP CODE	
Mull						

JOB TYPE Prod HOLE SIZE 7 7/8 HOLE DEPTH 5488 CASING SIZE & WEIGHT 5 1/2 15.5 lb
CASING DEPTH 5488 DRILL PIPE PC TOP #66 TUBING PC TOP #66 OTHER PC @ 2734
SLURRY WEIGHT 142 SLURRY VOL 129 1/2 WATER gal/sk 42.10 CEMENT LEFT IN CASING 42.10
DISPLACEMENT 129 1/2 DISPLACEMENT PSI 3 MIX PSI 3 RATE 3

REMARKS: safety meeting, ran float equip, and T #3 turbos 3, 3, 4, 5
22, 23, 24, 25, 27, 28, 29, 30, 32, 33, 37, 38, 39, 40 cent 65, 67
PC TOP #66, ran pipe to bottom, 1315' total & circulated for
2 hrs, pumped 56 bl water flush 56 bl water, mixed 10 SKS & 10 SKS M H,
mixed 230 SKS OWC 5# Kol-seal down center, released plug & displaced
with 127 bl water with a lift of 100' & plug landed @ 1600', released
pressure, float held, washed out pump & lines, rigged chd.

Thank You
Walt, Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401D	1	PUMP CHARGE	3400.00	3400.00
5406	75	MILEAGE	5.35	393.75
1126	250	OWC	33.70	8925.00
1110A	1250#	Kol-seal	.56	700.00
5407A	11.25	Ten mileage	1.75	154.25
1111A	300#	Sodium Metasilicate	2.63	504.00
1102	240#	Calcium chloride	.94	225.60
4203	1	5 1/2 Guideshoe (I)	202.75	202.75
4177	1	5 1/2 AF4 Floatcollar (w)	463.00	463.00
4406	1	5 1/2 rubber Plug	92.50	92.50
4136	18	5 1/2 Turbalizer (I)	25.75	1363.50
4130	2	5 1/2 centralizer (I)	61.00	122.00
4104	1	5 1/2 basket (w)	290.00	290.00
4285	1	5 1/2 Portcollar (I)	2178.75	2178.75
				17,405.60
				1,740.36
				15,663.24
				830.83
				11,494.07

completed

Ravin 3737

AUTHORIZATION

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 38056
LOCATION Oakley, KS
FOREMAN Kelly Gabel

DATE		CUSTOMER #		WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
8-13-13		5659		APC Baughman Unit 1-35		35	16 ^s	415 ^W	Cheyenne
CUSTOMER				Mull					
MAILING ADDRESS						TRUCK #	DRIVER	TRUCK #	DRIVER
						399	Damon		
						529	Jeremy		
CITY				STATE		ZIP CODE			
						Stevens		O. Ride along	

JOB TYPE <u>223 collar</u>	HOLE SIZE _____	HOLE DEPTH <u>5488</u>	CASING SIZE & WEIGHT <u>5 1/2 15.5 #</u>
CASING DEPTH <u>5488</u>	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER <u>PC @ 2734</u>
SLURRY WEIGHT <u>122-14</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>15661</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on well, pressured tool to 1000#, opened tool & checked for blow, mixed 400SKS CMD displaced with 15 bbl water, shut tool & pressured to 1000#, ran BIT + tubing, reversed out, washed out pump & lines, rigged down. cement did not circulate

Thank You
Kelly & Drew

[illegible]

Rayin 3737

AUTHORIZTION

TITLE

DATE 8-13-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.