

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400434931

Date Received:

07/22/2013

PluggingBond SuretyID

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()

Email: liz.lindow@pdce.com

7. Well Name: Harvesters Resources Well Number: 15R-403

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11720

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 15 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.494680 Longitude: -104.756420

Footage at Surface: 330 feet FNL/FSL 638 feet FEL/FWL
 FNL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4815 13. County: WELD

14. GPS Data:

Date of Measurement: 05/17/2013 PDOP Reading: 1.3 Instrument Operator's Name: Tom Carlson

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 734 FNL 1374 FEL 500 FSL 1374 FEL
 Sec: 15 Twp: 6N Rng: 66W Sec: 15 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 318 ft

18. Distance to nearest property line: 300 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 438 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

W2NE of Sec 15 T6N R66W. Horizontal wellbore crosses multiple lease lines within drilling and spacing unit. Distance to mineral lease line is 0'. Distance to unit boundary is 500'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility

Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	830	875	0
1ST	8+3/4	7	26	0	7266	650	7266	500
1ST LINER	6+1/8	4+1/2	11.6	6551	11720			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, E2 of Sec 15 T6N R66W. Proposed spacing unit map and 30-day certificate is attached. Distance to nearest well measured to via the Anti-Collision Report in the Deviated Drilling plan.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Liz Lindow

Title: Regulatory Analyst

Date: 7/22/2013

Email: liz.lindow@pdce.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee

Director of COGCC

Date: 9/8/2013

API NUMBER

05 123 37918 00

Permit Number: _____

Expiration Date: 9/7/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type	Description
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara and from 200' below and 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
	Operator must meet water well testing requirements per Rule 318A.
	Operator acknowledges the proximity of the Anderson #1-10-6-66 API #05-123-11374, the Blackgold #3, API #05-123-16318, the Pinnacle Park #13-14 API #05-123-12483, the 146 Company #14-1 API# 05-123-11464, the Ann #1, API #05-123-19345, the Jeff #1, API #05-123-17108, the Berg #15-16G6 API #05-123-18774, the Harvester #31-15 API #05-123-24269, the Berg #33-15 API #05-123-12966, and the Berry #22-2 API #05-123-17239 wells; operator agrees to: provide mitigation option 1, 2 or 3 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
400434931	FORM 2 SUBMITTED
400445724	DIRECTIONAL DATA
400445725	WELL LOCATION PLAT
400445734	PROPOSED SPACING UNIT
400445735	DEVIATED DRILLING PLAN
400445737	30 DAY NOTICE LETTER
400445738	EXCEPTION LOC REQUEST
400445740	EXCEPTION LOC WAIVERS
400452324	OFFSET WELL EVALUATION

Total Attach: 9 Files

General Comments

User Group	Comment	Comment Date
Permit	Ready to pass pending public comment.	7/25/2013 1:30:24 PM
Permit	Form passes completeness.	7/23/2013 9:22:56 AM

Total: 2 comment(s)

Best Management Practices

No	BMP/COA Type	Description