



CEMENTER'S WELL SERVICE, INC.
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200692

Date <u>9/25/12</u>	Well Owner <u>Great Western</u>	Well No. <u>26-23</u>	Lease <u>Andrews</u>
County <u>Weld</u>	State <u>Colorado</u>	Field	
Charge to <u>CADE Drilling LLC</u>	Code		Charge Code
Address <u>3450 WCR 27 #2 (CADE #25)</u>	For Office Use Only		
City, State <u>FT. Lupton Colorado 80421</u>			
Pump Truck No. <u>208</u>	Code	Bulk Truck No. <u>217</u>	Code
Type of Job	Depth	Ft. <u>743</u>	To
Surface <u>8 5/8" CSG-24"</u>	Bottom of Surface	Ft. <u>732</u>	To
Plug	Plug Landed @ <u>690</u>	Ft.	Time On <u>0130</u>
Production	Pipe Landed @ <u>732</u>	Ft.	Time Off <u>Plug Down 0330</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat ✓	<u>520</u>	<u>SK5</u>				
	Poz. Mix						
	Calcium Chloride	<u>3%</u>					
	Gel % Flo-Cele <u>1/4</u> #Per Sack						
	Handling Charge						
	Hauling Charge						
	Additional Cement						
<u>8 5/8"</u>	Centralizers	<u>3</u>					
	Cement Basket	<u>1</u>					
	Guide Shoe	<u>1</u>					
	Baffle Plate	<u>1</u>					
	Box-thread lock	<u>1</u>					
	Mix Rate <u>4 BPM</u>	Slurry Vol- <u>1.18 FT³</u> Sk-water Temp - <u>71° F</u>					
	Disp Rate <u>5 BPM</u>	Slurry WT <u>15.2 PPG</u>					
	Plug landed @ <u>450 PSI</u>	Total Slurry Vol- <u>109.2 BBL Cement</u>					
Remarks: <u>Pre-Flush w/ 20 BBL H₂O</u>	Tax Reference Code	Sub Total					
<u>Displace w/ 43.8 BBL H₂O</u>	State <u>CO 2.9 %</u>	Tax					
<u>Circulate 4 BBL Cement</u>	Disc.	Total					
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage

