

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400446878

Date Received:

07/16/2013

PluggingBond SuretyID

20030110

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

3. Name of Operator: WHITING OIL AND GAS CORPORATION 4. COGCC Operator Number: 96155

5. Address: 1700 BROADWAY STE 2300
City: DENVER State: CO Zip: 80290

6. Contact Name: Michael Brown Phone: (307)237-9310 Fax: ()
Email: ml_brown@bresnan.net

7. Well Name: Razor Well Number: 27J-2212B

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 13745

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 27 Twp: 10N Rng: 58W Meridian: 6

Latitude: 40.808444 Longitude: -103.848708

Footage at Surface: 2244 feet FSL 1948 feet FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4764 13. County: WELD

14. GPS Data:

Date of Measurement: 03/15/2013 PDOP Reading: 1.4 Instrument Operator's Name: Jeremy Harris

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2466 FNL 1707 FEL 100 FNL 1485 FEL
Sec: 27 Twp: 10N Rng: 58W Sec: 22 Twp: 10N Rng: 58W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 3337 ft

18. Distance to nearest property line: 404 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 265 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-314	960	N/2 S27, All S22

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

25. Distance to Nearest Mineral Lease Line: 0 ft26. Total Acres in Lease: 160**DRILLING PLANS AND PROCEDURES**27. Is H2S anticipated? Yes No If Yes, attach contingency plan.28. Will salt sections be encountered during drilling? Yes No29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No31. Mud disposal: Offsite Onsite**If 28, 29, or 30 are "Yes" a pit permit may be required.**Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	16+1/16	16	65	0	80			
SURF	13+1/2	9+5/8	36	0	1550	743	1550	0
1ST	8+3/4	7	29	0	6055	424	6055	0
1ST LINER	6	4+1/2	11.6	5237	13745			

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments The casing will be driven. There are no existing wells within 500 feet of the well bore. Wells Planned within 500 feet are shown on the multi-well plan map.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Michael L. BrownTitle: AgentDate: 7/16/2013Email: ml_brown@bresnan.net

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 9/17/2013

API NUMBER
05 123 38060 00

Permit Number: _____ Expiration Date: 9/16/2015**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type	Description
	1) Provide 48 hour notice prior to spud via electronic Form 42. 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
2157235	SURFACE AGRMT/SURETY
2234046	EXCEPTION LOC REQUEST
400446878	FORM 2 SUBMITTED
400446953	WELL LOCATION PLAT
400446973	DRILLING PLAN
400446980	DEVIATED DRILLING PLAN
400448244	DIRECTIONAL DATA

Total Attach: 7 Files

General Comments

User Group	Comment	Comment Date
Permit	Attached SUA. No LGD or public comments. Final Review--passed.	9/16/2013 8:16:42 AM
Permit	Per operator attached exception location request and waivers. Requested information on the right to construct since the minerals under the surface will not be produced.	9/9/2013 9:14:59 AM
Permit	On hold pending exception location waivers.	8/13/2013 3:44:33 PM
Engineer	No existing wells within 1500' of proposed directional.	7/29/2013 3:41:30 PM

Total: 4 comment(s)

Best Management Practices

No	BMP/COA Type	Description
1	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with oil and gas development throughout the State of Colorado. BMPs will be constructed as necessary to prevent stormwater from leaving the construction site. BMPs used will vary according to the location, and will remain until the pad is reclaimed.
2	Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with oil and gas operations throughout the State of Colorado.</p> <ul style="list-style-type: none">• Materials and fluids will be stored in a neat and orderly fashion.• Waste will be collected regularly and disposed of at an offsite facility.• Prompt cleanup is required of spills to minimize waste materials entering the stormwater runoff.• Drip pans will be used during fueling and maintenance to contain spills or leaks.• Cleanup of trash and discarded material will be done at the end of the work day.• Cleanup will consist of monitoring the road, location and any other work areas.• Material to be cleaned up includes trash, scrap, and contaminated soil.

Total: 2 comment(s)