

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400450057

Date Received:

07/25/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: ()

Email: bonnie.lamond@encana.com

7. Well Name: Woolley-Becky Well Number: 2D-7H-E168

8. Unit Name (if appl):  Unit Number:

9. Proposed Total Measured Depth: 14525

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 7 Twp: 1N Rng: 68W Meridian: 6

Latitude: 40.066690 Longitude: -105.053010

Footage at Surface: 2302 feet FNL 688 feet FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4996 13. County: WELD

14. GPS Data:

Date of Measurement: 05/22/2013 PDOP Reading: 2.5 Instrument Operator's Name: John Rice

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 1732 FNL 1259 FWL 460 FNL 1125 FWL  
Sec: 7 Twp: 1N Rng: 68W Sec: 6 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 305 ft

18. Distance to nearest property line: 322 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 63 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T1N R68W SEC 7: N/2 and other lands. Horizontal Wellbore crosses lease lines within drilling and spacing unit; distance to unit boundary is at least 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 317

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	7936	450	7936	500
2ND	6+1/8	4+1/2	13.5	0	14525	262	14525	7636

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Encana Oil & Gas (USA) Inc. requests the approval of a 318A.a.(1) and 318A.c.(2) exception location as the well head is to be located outside of a GWA drilling window and further than 50' from an existing well. Request letter attached. This well is closer than 150' to the nearest permitted or producing BHL. A 318A.m. variance request letter and waivers are attached. Encana Oil & Gas (USA) Inc. also requests the approval of the omission of open hole logs, request letter attached. Proposed unit configuration is T1N R68W Section 6: W/2; Section 7: NW/4. Subject location falls outside Town of Erie border, however, will adhere to Erie BMPs; see attachment.

34. Location ID: 305447

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Bonnie Lamond

Title: Permitting Analyst

Date: 7/25/2013

Email: bonnie.lamond@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 9/19/2013

#### API NUMBER

05 123 38107 00

Permit Number: \_\_\_\_\_

Expiration Date: 9/18/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<b>COA Type</b>	<b>Description</b>
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.. 2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log. 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
	Operator acknowledges the proximity of the Woolley A 1-7 (123-09093) and Thomas E Unit 2 (123-12370) wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.
	Operator must meet water well testing requirements per Rule 318A.

### **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

### **Attachment Check List**

<b>Att Doc Num</b>	<b>Name</b>
1695863	EXCEPTION LOC REQUEST
400450057	FORM 2 SUBMITTED
400452111	PROPOSED BMPs
400454869	30 DAY NOTICE LETTER
400454870	MINERAL LEASE MAP
400454871	DEVIATED DRILLING PLAN
400454873	OFFSET WELL EVALUATION
400454875	PROPOSED SPACING UNIT
400454878	VARIANCE REQUEST
400454879	WELL LOCATION PLAT
400454881	OTHER
400454884	DIRECTIONAL DATA
400459315	EXCEPTION LOC WAIVERS
400459316	EXCEPTION LOC WAIVERS

Total Attach: 14 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	9/19/2013 1:38:10 PM
Permit	Received and attached corrected Exception Loc & Twinning Request letter and added Location ID# 305447. ok to pass.	9/5/2013 1:54:53 PM
Permit	ON HOLD: Requesting corrected Rule #'s on Exception Loc Request letter. Add Location ID #.	8/27/2013 9:17:58 AM
Permit	Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Request and waivers attached.	8/27/2013 9:17:57 AM
Permit	Operator's request for omission of open hole logs.	8/27/2013 9:17:55 AM
Permit	Horizontal wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is 460'.	8/27/2013 9:17:54 AM
LGD	The Town of Erie concurs with the EnCana Oil Gas (USA) Inc. request that the Erie BMP's identified on Form 2 and attached thereto, be conditions of approval of the issuance of this permit.	8/7/2013 10:53:36 AM
Permit	Right to construct is O&G lease. This form has passed completeness.	7/30/2013 11:35:58 AM
Permit	Returned to draft. No right to construct given.	7/26/2013 12:54:47 PM

Total: 9 comment(s)

## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed well path with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
2	Drilling/Completion Operations	Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.

Total: 2 comment(s)