

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400466522

Date Received:

08/14/2013

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Michele Weybright

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 6298449

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-21828-00

6. County: GARFIELD

7. Well Name: Goldsborough

Well Number: PA 411-11

8. Location: QtrQtr: SENW Section: 11 Township: 7S Range: 95W Meridian: 6

Footage at surface: Distance: 2402 feet Direction: FNL Distance: 2052 feet Direction: FWL

As Drilled Latitude: 39.452913 As Drilled Longitude: -107.967398

GPS Data:

Data of Measurement: 12/20/2012 PDOP Reading: 2.1 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 813 feet. Direction: FNL Dist.: 653 feet. Direction: FWL

Sec: 11 Twp: 7S Rng: 95W

** If directional footage at Bottom Hole Dist.: 812 feet. Direction: FNL Dist.: 626 feet. Direction: FWL

Sec: 11 Twp: 7S Rng: 95W

9. Field Name: PARACHUTE

10. Field Number: 67350

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/06/2013 13. Date TD: 05/13/2013 14. Date Casing Set or D&A: 05/15/2013

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8230 TVD** 7758 17 Plug Back Total Depth MD 8170 TVD** 7698

18. Elevations GR 6275 KB 6296

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN/MUD/ CBL AND RESERVOIR PERFORMANCE MONITOR (RPM)

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	63	22	0	63	VISU
SURF	13+1/2	9+5/8	32.3	0	1,167	320	0	1,167	VISU
1ST	8+3/4	4+1/2	11.6	0	8,209	1,195	3,320	8,209	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,484		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,768		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,127		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,102		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

SISP # 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Michele L Weybright

Title: Permit Technician I

Date: 8/14/2013

Email: michele.weybright@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400467703	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400466540	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400466522	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400466542	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	PDF of CBL #700098017 in well file. Req'd PDF of triple combo log.	8/27/2013 12:19:25 PM

Total: 1 comment(s)