

PDC Energy
 Vetting 24-14
 SESW 14 5N 65W
 Weld County, CO
 Current Wellbore - NOT TO SCALE!!!
 9/23/2013

API#: 05-123-13068

GL Elevation: 4619

Surface Casing:
8 5/8" 24# @ 226' W/ 900 sks cmt.

First String
4 1/2" 11.6# @ 7040' w/ 175 sks cmt

Second String
50 sks cmt 3223'-6958', 235 sks cmt 0'-433'

Perforations	
Old:	Niobrara: 6656'-6911'
	Codell: 6912'-6979'
	0
	0
New:	0
	0
	0
	0

Sussex 4200'-4900

Top of Cement:
3233' / 0'

CIBP @ 6400'

Niobrara

Codell

PBTD:	7040
Casing TD:	0

NOTES

Set CIBP @ 6400 w/2 sx cement on top, set 50 sk stub plug at 6200', set 200 sk plug @ 3200, set plug from 500' to surface.