

Noble Energy, INC
State N36-09
05-123-15470

Current Wellbore Schematic

Status - DA
KB elev - 4874'
GL elev - 4864'

10 sk cmt plug @ surface

8 5/8" 24# sur csg set @ 302'
w/ 210 sks of cmt

50 sk cmt plug set 1/2 in and 1/2 out of sur csg

Base Fox Hills 518'

Deepest Water well: 900'

50 sk cmt plug set above backed-off prod csg @ 4750'

Prod csg backed-off @ 4750' (7 7/8" open hole to surface)

3 1/2" 9.3# set from 4750' to TD
w/ 200 sks of cmt

Codell: Perfs from 7352'-7373'

TD = 7456'