

**DRILLING PLAN**

**PWD Federal 21-6-91**

**Sec 21, T6S-R91W,**

**BLM Lease # COC-066370**

Dejour Energy (USA) presents the following Drilling Plan for the PWD Federal 21-6-91 well with a bottom hole location at lat. 39.508131143N, long. -107.5559195237W and surface location at lat. 39.508541N, long. -107.556063; located in the southeast quarter of Section 21, T6S, R91W. This well is located on BLM managed lands and is authorized under lease COC-066370. The proposed well will be drilled to a TD 4800 feet Measured Depth (MD) and a True Vertical Depth of 4606 feet (TVD).

In accordance with the requirements of Onshore Oil and Gas Order Number 1 (43 CFR 3162.3), the following detailed drilling plan is provided.

**Geologic Information for the Drilling Plan**

Formation Tops PWD Fed 21-6-91

<b>Formation</b>	<b>Sea Level Elevation</b>	<b>MD</b>	<b>TVD from Surface Pad</b>
Wasatch Formation	Ground 7008	0	0
Top Mesaverde Williams Fork SS	2575	4627	4433

Depth to Oil, Gas, Water & Minerals – PWD Fed 21-6-91


<b><u>Substance</u></b>	<b><u>Formation</u></b>	<b><u>Sea Level Elevation</u></b>	<b><u>MD</u></b>	<b><u>TVD from Surface Pad</u></b>
Water	Wasatch	7008	0	0
Gas	Williams Fork	2575	4627	4433

Note: The nearest water wells range, in bottom hole depths, from 5330 feet to 6330 feet above sea level. Casing design is to a consistent depth of 5200 feet above sea level.

# AQUAMAP

## Colorado Division of Water Resources Department of Natural Resources

Map created by xxx 6/20/2011



**LEGEND**

- Blue Squares are Oil and gas Wells
- Green Circles are Water Wells
- Red Circles are Undrilled Permitted Water Wells
- Red Squares are Dejour Proposed Well Pads

Number Labels indicate depth of well and the bottom hole elevation above sea level

Colorado River is approximately 5480 feet above sea level at the Garfield Creek Confluence



Based on work developed at <http://www.carto.net>

Address location by Yahoo Maps  
AquaMap Version 3.0.1 July 5, 2009

2009  
 © L  
 Tra  
 S  
 O  
 T  
 A

34,894 ft

26,963 ft

### Well Control Equipment for wells drilled off of Pad 21A

1. Dejour Energy (USA) minimum specifications for pressure control are as follows:

Depth Range	Well Control Equipment
0 - 1200' (surface interval)	No Control
1200' – TD	11", 5000 psi ram type preventers with one set of blind rams, one set of pipe rams and 5000 psi annular type preventer with choke manifold as per attached diagram.
No abnormal temperatures or H <sub>2</sub> S gas are anticipated. No over-pressured intervals are expected.	


2. Dejour will comply with all requirements pertaining to well control as listed in Onshore Oil and Gas Order No. 2 as well as Colorado Oil and Gas Conservation Commission (COGCC) Rules and Regulations.
3. Dejour will comply with Onshore Oil and Gas Order No. 2 as well as COGCC regulations concerning the testing of blow out prevention (BOP) equipment to include the following:
  - a. Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 70% of internal yield pressure of casing if BOP stack is not isolated from casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. If a test plug is utilized, no bleed-off of pressure is acceptable. For a test not utilizing a test plug, if a decline in pressure of more than 10% in 30 minutes occurs, the test shall be considered to have failed. Valve on casing head below test plug shall be open during test of BOP stack.
  - b. All BOP tests will be performed by a tester and not by the rig pumps using clear water or an appropriate clear liquid for subfreezing temperatures. Annular type preventers shall be tested to 50% of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.
  - c. As a minimum, the above test shall be performed:
    - i. When initially installed;
    - ii. Whenever any seal subject to test pressure is broken;
    - iii. Following related repairs;
    - iv. At 30-day intervals; and
    - v. Valves shall be tested from working pressure side during BOP tests with all down-stream valves open.
  - d. When testing the kill line valve(s), the check valve shall be held open or the ball removed.
  - e. Annular preventers shall be functionally operated at least weekly.
  - f. Pipe and blind rams shall be activated each trip, however, this function need not be performed more than once a day.

- g. A BOP pit level drill shall be conducted weekly by each drilling crew.
- h. Pressure tests shall apply to all related well control equipment.
- i. All of the above described tests and/or drills shall be recorded in the drilling log.
- j. See Figure 3 for a typical BOP diagram.

**Figure 3: Typical Blowout Preventer Diagram**

5,000 psi BOP stack and 5,000 psi Choke Manifold will be minimum equipment. The actual dimensions and specifications will be determined when the drilling rig is selected.

**5M BOP Stack Schematic**



5M psi system:

- Double ram with blind rams and pipe rams\*
- Annular Preventers
- Drilling spool, or blowout preventer with 2 side outlets (choke side shall be a 3-inch minimum diameter, kill side shall be at least 2-inch diameter)\*
- Kill line (2 inch minimum)
- A minimum of 2 choke line valves (3 inch minimum)\*
- 3 inch diameter choke line
- 2 kill line valves, one of which shall be a check valve (2 inch minimum)\*
- 2 chokes (refer to diagram in Attachment 1)
- Pressure gauge on choke manifold
- Upper kelly cock valve with handle available
- Safety valve and subs to fit all drill string connections in use
- All BOPE connections subjected to well pressure shall be flanged, welded, or clamped\*
- Fill-up line above the uppermost preventer

**Casing Program**

Hole Size (in)	Casing/Tubing Size (in)	Wt. (#/ft)	Grade	Connection
13 ½	9 5/8"	32.2	H-40	STC
8 3/4	5 1/2"	15.5	J-55	LTC

9 5/8", 32.2#, H40, STC	Collapse	Burst	Tensile	ID
100%	1,400 psi	2,270 psi	254,000 lbs	9.001"
80%	1,120 psi	1,816 psi	203,200 lbs	8.845" drift

The surface casing string 9 5/8" will be centralized using bow spring centralizers. The bottom (3) joints of casing will be centralized, from that point up, one centralizer will be run on every third joint to surface.

5 ½", 11.6#, J-55, LTC	Collapse	Burst	Tensile	ID
100%	4,040 psi	4,810 psi	217,000 lbs	4.950"
80%	3,232 psi	3,848 psi	173,600 lbs	4.825" drift

The production casing 5 ½" will be centralized using bow spring centralizers as follows: Every joint for first 3 joints, every other joint to 1200' and every third joint from 1200 ft to surface.

**I. Cementing Program Casing and Cementing Program:**

**B. Surface Casing**

1. Hole Size: 13 ½"
2. Casing: Approximately 1200' of 9-5/8", 32.2#, H-40, ST&C casing.
3. Casing Hardware: 1 Guide Shoe, 1 Float Collar, 1 Stop Ring, 12 Centralizers, 1 Thread Lock, 2 Cement Baskets and 1 Top Plug.
4. Cement: Calculate for 75% excess to bring cement to surface with casing on bottom. Cement as follows:  
Lead: 335 sks Econocem w/ 2% CaCl<sub>2</sub>, 12.8 ppg, 2.11 ft<sup>3</sup>/sk yld  
Top job as required to fill 9-5/8" x 13 ½" annulus to surface with Premium Class G cement containing 2% Calcium Chloride. Wait on cement four hours before slacking off casing.

**C. Production Casing:**

1. Hole Size: 8 ¾"
2. Casing: Approximately 4800' of 5-1/2", 15.5#, J-55, LT&C casing.
3. Casing Hardware: 1 Float Shoe, 1 Float Collar, 1 Stop Ring, 57 Centralizers, 1 Thread Lock, 1 Bottom Plug, 2 Cement Baskets and 1 Top Plug.
4. Cement: 15% excess cement over hole volume to bring top of cement to a depth of 1000' (200' inside surface casing). Cement as follows:  
Lead: 250 sks Econocem at 12.3 ppg, 1.99 ft<sup>3</sup>/sk yld  
Tail: 525 sks Econocem at 12.8 ppg, 1.77 ft<sup>3</sup>/sk yld

A water quality analysis will be performed on the mix water used in cementing to ensure adequate cement properties.

**Mud Program**

<b>Interval</b>	<b>Mud Description</b>	<b>Weight</b>	<b>Viscosity</b>	<b>Wtr Loss</b>
Surface to 1200' MD	Spud Mud and LSND	8.4-8.8	<30 cp	Less than 15 cc's
1200' to 4800' MD	LSND	8.6-9.0	<35 cp	Less than 10 cc's at TD

Both electrical and mechanical fluid monitoring will be used to monitor the drilling fluid in the well bore. Each tank volume, flow rate, as well as total hole and surface volumes will be monitored on a continuous basis using a Mud Monitoring system.

A closed loop system shall consist of steel tanks and solids control equipment to hold the drilling fluid while the cuttings are routed to the cuttings trench.

Products to be used:

<b><u>Product</u></b>	<b><u>Description</u></b>	<b><u>Function</u></b>	<b><u>Concentration</u></b>
<i>New Bar</i>	Barium Sulfate	Weighting Material	As required for slugs and mud weight
<i>NewGel</i>	Bentonite	Viscosifier	15-20 ppb
<i>Caustic Soda</i>	Sodium Hydroxide	Alkalinity Control	0.15-0.25 ppb
<i>NewHPA</i>	PIPA	Viscosifier / Emulsifier	0.5 ppb
<i>NewPac</i>	Polyanionic Cellulose	Fluid Loss	0.5-1.0 ppb
<i>Soda Ash</i>	Na <sub>2</sub> CO <sub>3</sub>	Calcium Precipitant	As required
<i>Maxiseal</i>	LCM Blend	LCM Material	As required
<i>Sawdust</i>	Wood Fibers	LCM Material	As required
<i>NewCarb</i>	Calcium Carbonate	LCM Material	As required
<i>DynaFiber</i>	Microcellulose Fiber	LCM	As required
<i>NewEase</i>	Proprietary	ROP enhancer	As required
<i>KCl</i>	Potassium Chloride	Inhibitor	2%

### Logging Program

Type Log Suite	Interval Top	Interval Bottom
Resistivity	Base of surface casing	TD
Density-Neutron	Base of Surface Casing	TD
Gamma Ray	Surface	TD

### Coring Program

Core No.	Formation	Est. Depth ft	Core Length (ft)
None			

### Water Source

The freshwater required for the drilling operation will be purchased from West Divide Water Conservation District and pumped and trucked in from the nearest local water source on the Colorado River located South of Divide Creek and County Road 311 intersection . Estimated water usage is ~3000 bbls for drilling operations.

### Additional Information

- 1) Normal pressures are expected.
- 2) Maximum expected bottom hole pressure: 2000 psi
- 3) Maximum expected bottom hole temperature: 130 deg F
- 4) H2S is not expected.
- 5) 5 ½" 15.5# J-55 Test Casing Pressure 3800 psi
- 6) Frac Pressure 2800 psi w/ 0.62 frac gradient
- 7) The well will be directionally drilled. Please see Directional vertical section plan as well as the side view along with the trajectory for deviation program. Maximum angle is 30° with an Azimuth of 258.3°, KOP will be at 300 ft.
- 8) Bottom hole target will be a 100' radius.

Attached to Form 3160-3