



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 37931
LOCATION Oakley, KS
FOREMAN Kelly Gabel

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
6-28-13	6378	Harley #5		5	145	44W	Cheyenne
CUSTOMER				Cheyenne Wells			
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
CITY				399	Dane		
STATE				528	Tim		
ZIP CODE				5	Daniel (ride along)		

JOB TYPE <u>2-Port collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER <u>#1-4305</u>
SLURRY WEIGHT <u>142-125</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>#2-2530</u>
DISPLACEMENT <u>24 1/2 - 13 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety meeting on ECWS, rigged up on well, tested Tool to 1000#, checked for blow, mixed 100 sks OWC 270 CC, displaced with 24 1/2 bbl water, shut tool, ran 4 1/2" tubing, reversed out waited 3 hrs, pulled tubing to 2530, pressured tool to 1000#, opened tool to check for blow, mixed 250 sks 60/40 Poz 280 gel 270 CC & displaced with 14 bbl water, shut tool, reversed out, washed out pumps & lines, rigged down

Thank You
Kelly & crew

[illegible]

Ravin 3737

AUTHORIZATION Let He TITLE MAN. MEMBER DATE 6-28-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37921
LOCATION Chickley, KS
FOREMAN Jerry V (Trincee)
Fuzzy

FIELD TICKET & TREATMENT REPORT
CEMENT

Colorado

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-25-13	6378	Harley #5	5	145	44W	Cheyenne
CUSTOMER <u>Pronghorn Operating LLC</u>			Cheyenne Wells			
MAILING ADDRESS <u>Wto 43</u>			N to T			
CITY			ZIP CODE			
STATE			RATE			
JOB TYPE <u>long string</u>			HOLE SIZE <u>2 7/8</u>			
CASING DEPTH <u>5633.08</u>			DRILL PIPE			
SLURRY WEIGHT <u>14.2</u>			SLURRY VOL			
DISPLACEMENT <u>133.8</u>			DISPLACEMENT PSI			
REMARKS:			Safely meeting & rig up on Wildcat #1 run flat ega. centerizers on 2, 3, 7, 35			
			turbolizers on 4, 5, 6, 32, 34 baskets on 32 & 74 & p.c. on top of 32 @ 4313.46, and			
			p.c. on top of jt 74 @ 2542.92 run pipe hook up to mudline & broke circulation ball went thru			
			@ 550# with good returns pump 500 gal mud flush mixed 5 sks in rat, 5 sks mouse, 150 sks			
			OWC with 5# Kol seal & 1/2# flo seal persack shutdown wash put pump & lines release plug			
			displaced with 133 bbl fresh water plug landed @ 2000# psi with a 1600# lift released			
			back & float held shut in and rig down & done			

Thanks - Jerry & crew
Fuzzy Too 😊

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3400.00	3400.00
5406	85	MILEAGE	5.25	446.25
5407A	7.5	Ton Mileage delivery	175	1115.63
1126	160 sks	OWC	23.70	3792.00
1110A	800 #	Kol seal	.56	448.00
1107	80 #	Flo seal	2.97	237.60
1144G	500 gal	WFR mud Flush	1.00	500.00
4159	1	5 1/2 AFU Flop shoe (W)	433.75	433.75
4454	1	5 1/2 latch down assy	318.25	318.25
4130	4	5 1/2 centerizers W	61.00	244.00
4136	5	5 1/2 turbolizers W	75.75	378.75
4104	2	5 1/2 baskets W	290.00	580.00
4285	2	5 1/2 Port Collars F	2178.75	4357.50
		Subtotal		16251.73
		less 10% disc.		- 1625.17
		Subtotal		14,626.56
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 40018
LOCATION Oakley, KS
FOREMAN Kelly Gohel

FIELD TICKET & TREATMENT REPORT

6010

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
6-17-13	4595	Harley #5		5	14	44	Cheyenne
CUSTOMER				Cheyenne Wells			
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
Pronghorn				399	Damon		
				528	Jeremy		
CITY		STATE	ZIP CODE				

JOB TYPE	Surface (cond.)	HOLE SIZE	17 1/2	HOLE DEPTH	436	CASING SIZE & WEIGHT	13 3/8 33 #
CASING DEPTH	429'	DRILL PIPE		TUBING		OTHER	
SLURRY WEIGHT	148	SLURRY VOL		WATER gal/sk		CEMENT LEFT in CASING	30'
DISPLACEMENT	62 1/2	DISPLACEMENT PSI		MIX PSI		RATE	

REMARKS: Safety meeting, rigged up on widecat + drilling, hooked up to circulate, mixed 400 sacks Com 3% CC 2% gel + displaced with 62 1/2 bbl water. dropped plug — washed out pump + lines rigged down. Cement did circulate

Approx 30001 topit

Thank You
Kelley & Crew

[illegible]

Ravin 3737

AUTHORIZATION Josh KH TITLE DR. JOSHUA K. HARRIS DATE 6-17-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.