

STAGE CMT - upper + lower

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37941
LOCATION Rockledge, RS
FOREMAN Kelly Gabel
PORT Walt D. Inghel

FIELD TICKET & TREATMENT REPORT

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
7-10-73		Harley #4		5	14 th	44 th	Cheyenne
CUSTOMER Ponghorn				Cheyenne Wells			
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
				388	T Davis		
				528	Gene		
CITY		STATE	ZIP CODE				

JOB TYPE <u>Double Portoker</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER <u>PC@ 4301 + 2539</u>
SLURRY WEIGHT <u>142-125</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>24 + 133/4</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on well, pressured tool to 1000#, opened tool & checked for blow, pumped 20 bbl water, mixed 100SKS OWC 200 cc displaced with 24 bbl water, shut tool, pressured to 1600#, ran 4 1/2" tubing & reversed out, waited 3 hrs, pressured top Port collar to 1600# opened tool, checked for blow, pumped 20 bbl water, mixed 250SKS 60/40 P02 800gel 200 cc & displaced with 13 3/4 bbl water, shut tool pressured to 1000#, ran 4 1/2" tubing to reverse out, washed out pump & lines, rigged down.

Thank You
Walt, Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401B	1	PUMP CHARGE	1785 ⁰⁰	1785 ⁰⁰
5406	85 mi	MILEAGE	525	446 ²⁵
1126	100 SKS	OWC	2370	2370 ⁰⁰
1102	188#	Calcium chloride	.94	176 ⁷²
1131	250	60/40 Pdz	1586	3965 ⁰⁰
1118B	1720#	Bentonite	.27	464 ⁴⁰
1102	430#	calciumchloride	.94	404 ²⁰
5407A	15.45	Ton mileage delivery	175	2298 ¹⁹
				11,909 ⁵²
			low 10070	1,590 ⁹⁶
				10,718 ⁵⁶
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

AUTHORIZTION

TITLE

DATE 7-10-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37924
LOCATION Oakley, KS
FOREMAN Jerry V. (Trainee)
Fuzzy

FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-7-13	6378	Harley #4	5	14S	44W	Colorado Cheyenne
CUSTOMER <u>Pronghorne</u>			Cheyenne Wells West 4043 N to S 1/4 E N into			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			463	Cory D		
			693	Jack J		
CITY						
STATE						
ZIP CODE						

JOB TYPE logging HOLE SIZE 7 1/8 HOLE DEPTH 5570 CASING SIZE & WEIGHT 5 1/2" 15.5#
CASING DEPTH 5565.93 DRILL PIPE TUBING OTHER 133 total jts
SLURRY WEIGHT 14.2 SLURRY VOL WATER gal/sk CEMENT LEFT in CASING 10.45'
DISPLACEMENT 132 1/4 DISPLACEMENT PSI MIX PSI RATE

REMARKS: Safety meeting & rig up on Wildcat #1 run that against centralizers on 1, 5, 6, 30 33, 72, 75, turbolizers on 2, 3, 4, 32 74 baskets on bottom of 31 & 73, port collars on top of 31 @ 4300.89 & on top of 73 @ 2539.56 fill pipe @ 1480 run pipe hook up to mud tree and pump ball then mixed 2 bbl in mh, 2 bbl in rat hole, mixed 190 sks OWC w/ 5# Kol seal per sk & 1/2# Flo Seal shutdown clean pump & liner released plug displaced with 135 1/2 bbl got returns 125 bbl final lift 700 plug landed @ 1200# released plug float held - pressured back up to 500# & shut in for 15 min plug down @ 8' 10" mud. run 5 bbl water, mud flush, & 5 bbl water before mixing cement Thanks Jerry, Fuzzy & CREW

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3400 ⁰⁰	3400 ⁰⁰
5406	8.5	MILEAGE	5.35	4146 ²⁵
5407A	9.4	Ton mileage delivery	1.75	1398 ²⁵
1126	200 sks	OWC	23.20	41740 ⁰⁰
1110A	1000#	Kol seal	.56	560 ⁰⁰
1107	100#	Flo Seal	2.97	297 ⁰⁰
1144G	500 gal	WFR mud Flush	1.00	500 ⁰⁰
4159	1	5 1/2 AFU Float shoe I	433 ⁷⁵	433 ⁷⁵
4454	1	5 1/2 latchdown gssy	318 ²⁵	318 ²⁵
4130	7	5 1/2 centralizers W	61 ⁰⁰	427 ⁰⁰
4136	5	5 1/2 turbolizers W	75 ⁷⁵	378 ⁷⁵
4104	2	5 1/2 baskets W	290 ⁰⁰	580 ⁰⁰
4285	2	5 1/2 port collars I	2178 ⁷⁵	4357 ⁵⁰
			Subtotal	17,836 ⁷⁵
			less 10%	1,783 ⁶²
			Subtotal	16,053 ⁰⁰
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

AUTHORIZATION [Signature]

TITLE MAN. MEMBER

DATE 7/7/13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



FIELD TICKET & TREATMENT REPORT

TICKET NUMBER 37932
LOCATION Oakley, KS
FOREMAN Kelly Gable

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
6-28-13	6378	Harley #4		5	145	44W	Cheyenne
CUSTOMER				Cheyenne Wells			
MAILING ADDRESS				TRUCK #	DRIVER	TRUCK #	DRIVER
Pronghorn							
CITY							
STATE		ZIP CODE					

JOB TYPE <u>Surface</u>	HOLE SIZE <u>17 1/2</u>	HOLE DEPTH <u>445</u>	CASING SIZE & WEIGHT <u>13 3/8 - 48#</u>
CASING DEPTH <u>438</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>30'</u>
DISPLACEMENT <u>64601</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety meeting, rigged up on wildcat drilling, hooked up to circulate, mixed 3755K5 com 320 cc 25% goil, released plug displaced with 64 bbl water, shut in, washed out pumps & lines rigged down.

Cement did circulate

Approx 24661 to pit

Thank You
Keller crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	1785 ⁰⁰	1785 ⁰⁰
5406	85 mi.	MILEAGE	535	446 ²⁵
11045	375	class A cement	18 ⁵⁵	6956 ²⁵
1102	1052#	Calcium chloride	.94	993 ⁵⁸
1118B	705#	Bentonite	.27	190 ³⁵
5467A	17.62	Ton mileage delivery	175	2621 ⁷²
44116	1	13 ³ / ₈ rubber plug	433 ⁷⁵	433 ⁷⁵
				13,426 ⁹⁰
			1090	1,342 ⁶⁹
				12,084 ²¹
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

AUTHORIZTION

TITLE

Tool pusher

DATE 6-28-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.