



02055851



State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



FOR OFFICE USE ONLY

RECEIVED

SEP 13 2013

COGCC**LOSS OF WELL CONTROL REPORT**

As required by Rule 327.

1. OGCC Operator Number: 96850	4. Contact Name & Phone Doug McAdam	Report taken by: Kinzie Beavers DAVE ANDREWS
2. Name of Operator: WPX Energy Rocky Mountain LLC.	Ph: 970 618 7340	
3. Address: 1001 17th St., Suite 1200 City: Denver State: CO Zip: 80202	Fax:	

WELL LOCATION INFORMATION

5. API Number: 05-045-21848-00	6. County: Garfield
7. Well Name: Savage	8. Well Number: RWF 21-35
9. Unit Name (if appl.):	10. Unit No:
11. QtrQtr: NWNW Sec: 35 Twp: 6S Rng: 94W Meridian: 6	
12. Footage From Exterior Section Lines: 1171' FNL 1195' FWL	
13. Field Name: Rulison	14. Field Number: 75400

CASING INFORMATION

15. Surface Casing Size: 9 5/8 Weight per Foot: 32.3 Grade: H 40 True Vertical Setting Depth: 1151'
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

KICK INFORMATION

17. True Vertical Depth at Kick: 7801'	19. Formation Code: RLNS
18. Formation at Kick: Rollins Sandstone	
20. Shut-in Drill Pipe Pressure (SIDPP): 400 psi.	
21. Shut-in Casing Pressure (SICP): 0 psi.	
22. Mud Weight at Time of Kick: 12.1 ppg.	
23. Pit Gain: 60 bbls.	
24. Time and Date Shut In: 09/11/13 10:00	
25. Mud Weight Required to Control Well: 12.3 ppg.	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail): On RWF 21-35, API #05-045-21848-00, at a TVD of 7801 ft at 10:00, a 60 bbl mud pit gain was observed, and a soft shut in was performed. Choke was shut in, recorded SIDPP = 400 psi, casing pressure = 0 psi. Mud weight at time of kick was 12.1 ppg. Circulated out gas from mud, mud weight was brought up to 12.3 ppg, and choke was fully open, after shutting down mud pumps and observing no flow. Drilling operations then resumed.	