

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400447640

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: PA

Well Number: 421-7

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

COGCC Operator Number: 96850

Address: 1001 17TH STREET - SUITE #1200

City: DENVER

State: CO

Zip: 80202

Contact Name: ANGELA
NEIFERT-KRAISER

Phone: (303)606-4398

Fax: (303)629-8268

Email: ANGELA.NEIFERT-KRAISER@WPXENERGY.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20030107

WELL LOCATION INFORMATION

QtrQtr: LOT 10 Sec: 6 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.461727

Longitude: -108.046525

Footage at Surface: 713 feet FNL/FSL FSL 771 feet FEL/FWL FWL

Field Name: PARACHUTE

Field Number: 67350

Ground Elevation: 5152

County: GARFIELD

GPS Data:

Date of Measurement: 06/19/2008 PDOP Reading: 3.4 Instrument Operator's Name: MICHAEL LANGHORNE

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 584 FNL 1600 FWL 584 FNL 1600 FWL
 Sec: 7 Twp: 7S Rng: 95W Sec: 7 Twp: 7S Rng: 95W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.(check all that apply) ☒ is committed to an Oil and Gas Lease.☒ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

SEE ATTACHED

Total Acres in Described Lease: 246 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 21 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1107 Feet
Building Unit: 1501 Feet
High Occupancy Building Unit: 1606 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 362 Feet
Above Ground Utility: 265 Feet
Railroad: 390 Feet
Property Line: 231 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 456 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 584 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	440-61	320	N/2

DRILLING PROGRAM

Proposed Total Measured Depth: 6799 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 456 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Centralized E&P WMF

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

RE-USE & EVAP & BACKFILL

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48	0	60	50	60	0
SURF	13+1/2	9+5/8	32.3	0	1069	283	1069	0
1ST	8+3/4	4+1/2	11.6	0	6799	809	6799	3450

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

--

Location ID: 335035

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: ANGELA NEIFERT-KRAISER

Title: REGULATORY SPECIALIST Date: Email: ANGELA.NEIFERT-

COGCC Approved: _____ Director of COGCC _____ Date: _____

Expiration Date:

05

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Description

--	--

Best Management Practices

No	BMP/COA Type	Description
1	Planning	<ul style="list-style-type: none"> * Maximize the utility of surface facilities by developing multiple wells from a single pad (directional drilling), and by co-locating multipurpose facilities (for example, well pads and compressors) to avoid unnecessary habitat fragmentation and disturbance of additional geographic areas. * Maximize the use of directional drilling to minimize habitat loss/fragmentation * Maximize use of remote completion/frac operations to minimize traffic * Maximize use of remote telemetry for well monitoring to minimize traffic
2	General Housekeeping	<p>Although this location is located within 500 ft. of perennial, ephemeral, or intermittent surface water according to USGS mapped surface waters, the attached Sensitive Area Determination concludes that the location is not within a sensitive area due to the low potential for impacts to surface water in the case of a facility release. However, in order to satisfy COGCC guidance requiring that all locations within 500 ft. of mapped surface water incorporate BMPs to protect that surface water, Williams will employ the following BMPs at this location:</p> <ul style="list-style-type: none"> • Williams will ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations. • Williams will implement best management practices to contain any unintentional release of fluids. • Either a lined drilling pit or closed loop system will be implemented.
3	Drilling/Completion Operations	<ul style="list-style-type: none"> * Conduct well completions with drilling operations to limit the number of rig moves and traffic.
4	Interim Reclamation	<ul style="list-style-type: none"> * Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife * WPX Energy will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas. * Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings. * Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.

Total: 4 comment(s)

Date retrieval failed for the subreport 'IntPolicy_MTO' located at: W:\Electpub\Nat\Reports\policy_mto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400447647	DIRECTIONAL DATA
400447648	DEVIATED DRILLING PLAN
400447650	WELL LOCATION PLAT
400489212	LEASE MAP
400489213	ACCESS ROAD MAP
400489214	SURFACE AGRMT/SURETY
400489233	LEGAL/LEASE DESCRIPTION
400489241	LEGAL/LEASE DESCRIPTION

Total Attach: 8 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)