

PDC Energy  
 McCarty 28-3  
 NENW 28 4N 67W  
 Weld County, CO  
 Current Wellbore - NOT TO SCALE!!!  
 10/3/2013

API#: 05-123-12946

GL Elevation: 4968

Surface Casing:
9 5/8" 32# @ 308' W/ 270 sks cmt.

First String
2 7/8" 6.4# @ 7465' w/ 315 sks cmt

Second String
0

Perforations	
Old:	Niobrara: 7013'-7203'
	Codell: 7322'-7333'
	0
	0
New:	0
	0
	0
	0

Parkman/Sussex 3500-4000'

Top of Cement:
6340'

CIBP @ 6913
-------------

Niobrara
----------

Codell
--------

PBTD:	7343
Casing TD:	0

#### NOTES

Set CIBP @ 6913 w/2 sx cement on top, cut casing at 6240', set 50 sk stub plug at 6240', set 200 sk plug @ Parkman/Sussex, set plug from 500' to surface.