

PDC Energy
 McCarty 28-4
 SENW 28 4N 67W
 Weld County, CO
 Current Wellbore - NOT TO SCALE!!!
 10/3/2013

API#: 05-123-12947

GL Elevation: 4966

Surface Casing:
8 5/8" 24# @ 310' W/ 310 sks cmt.

First String
2 7/8" 6.4# @ 7475' w/ 360 sks cmt

Second String
0

Perforations	
Old:	Niobrara: 7025'-7194'
	Codell: 7335-7341'
	0
	0
New:	0
	0
	0
	0

Parkman/Sussex 3500-4000'

Top of Cement:
5940

CIBP @ 6925'

Niobrara

Codell

PBTD:	7418
Casing TD:	0

NOTES

Set CIBP @ 6925 w/2 sx cement on top, cut casing at 5840', set 50 sk stub plug at 5840', set 200 sk plug @ Parkman/Sussex, set plug from 500' to surface.