

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400413976

Date Received:

05/22/2013

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10275  
2. Name of Operator: AUGUSTUS ENERGY PARTNERS LLC  
3. Address: 2016 GRAND AVE STE A  
City: BILLINGS State: MT Zip: 59102  
4. Contact Name: Loni Davis  
Phone: (970) 332-3585  
Fax: (970) 332-3587

5. API Number 05-125-12015-00  
6. County: YUMA  
7. Well Name: Rockwell  
Well Number: 14-13 1S45W  
8. Location: QtrQtr: SWSW Section: 13 Township: 1S Range: 45W Meridian: 6  
9. Field Name: DUKE Field Code: 18890

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 05/07/2013 End Date: 05/07/2013 Date of First Production this formation: 05/08/2013

Perforations Top: 2274 Bottom: 2294 No. Holes: 40 Hole size: 47/100

Provide a brief summary of the formation treatment: Open Hole: ☐

Total usage of 49,920 16/30 Texas Gold sand, 50,000# 12/20 Texas Gold sand, & 505,000 scf N2.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 351 Max pressure during treatment (psi): 1896

Total gas used in treatment (mcf): 505 Fluid density at initial fracture (lbs/gal): 8.33

Type of gas used in treatment: NITROGEN Min frac gradient (psi/ft): 0.50

Total acid used in treatment (bbl): 12 Number of staged intervals: 6

Recycled water used in treatment (bbl): Flowback volume recovered (bbl): 424

Fresh water used in treatment (bbl): 339 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 99920 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/10/2013 Hours: Bbl oil: Mcf Gas: Bbl H2O:

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 121 Bbl H2O: 0 GOR: 0

Test Method: Flowing Casing PSI: 278 Tubing PSI: Choke Size: 5/8

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 996 API Gravity Oil: 0

Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Loni J. Davis

Title: Oper Acctg & Reg Spec Date: 5/22/2013 Email ldavis@augustusenergy.com  
:

### Attachment Check List

Att Doc Num      Name

400413976	FORM 5A SUBMITTED
-----------	-------------------

Total Attach: 1 Files

### General Comments

User Group      Comment      Comment Date

--	--	--

Total: 0 comment(s)