

PDC Energy
 McCarty 28-7
 SWNE 28 4N 67W
 Weld County, CO
 Proposed Wellbore - NOT TO SCALE!!!
 10/3/2013

API#: 05-123-13309

GL Elevation: 4932'

Surface Casing:
8 5/8" 24# @ 296' W/ 275 sks cmt.

First String
2 7/8" 6.4# @ 7420' w/ 450 sks cmt

Second String
0

Perforations	
Old:	Niobrara: 7022-7204'
	Codell: 7326-7336'
	0
	0
New:	0
	0
	0
	0

Parkman/Sussex 3500-4000'

Top of Cement:
5662

CIBP @ 6922'

Niobrara

Codell

PBTD:	7385'
Casing TD:	0

NOTES

Set CIBP @ 6922' w/2 sx cement on top, cut casing at 5562', set 50 sk stub plug at 5562', set 200 sk plug @ Parkman/Sussex, set plug from 500' to surface.