



Banner Oil Tools

SIGNATURE

Baker Oil Tools 810
S. Kansas Ave. Liberal
KS. 316-642-4955



Baker Oil Tools

Page : 1

OPERATOR	FAK #
Evergreen Operating Co	303-298-7800
COMPANIED	PHONE #
Shane Gagliardi	303-298-8100
FIELD	WELL NO
Vermejo Ranch	31-19
STATE	LEASE
Colorado	Vermejo Monitor Well
Tool Supervisor	PHONE #
Daniel L. Estes	620-624-4955
PICTURE	PHONE #
PREPARED BY	PHONE #
Daniel L. Estes	620-624-4955
DATE SUBMITTED	JOB # (VERSION #)
19-Jun-01	
JOB REPORT #	WELL TYPE
	Gas

SIP		BHT		Baker Oil Tools	
MAX DEV		CORE DEV			
CONCRETE TYPE				Page : 1	
SAND GRADE		COMPLETION FLUID (weight and type)		STARTING WELL	
PERFORATIONS				COATING (type)	
CASING	SIZE 5-1/2	WEIGHT 15.50	GRADE	THREAD	
LINER					
TUBING	2-7/8	6.40	N-80	EU 8rd	
WRKSTR.					

No.	DEPTH	LENGTH	OD	ID	DESCRIPTION
1	1,996	1.21	3.063	1.780	2 3/8 X 1.78 R Non Ported Seating Nipple w/1.728 no-go
2		2	3.063	1.995	2 3/8 X 2' Pup Joint
3	1,991	3.13	4.781	1.978	45B Model "AD-1" Tension Packer
4		32.5	3.063	1.995	1 Joint 2 3/8 Tubing
5	1995	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
6		6.09	3.063	1.995	2 3/8 X 6' Pup Joint
7	1,947	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
8		32.1	3.063	1.995	1 Joint 2 3/8 Tubing
9	1911	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
10		10.19	3.063	1.995	2 3/8 X 4' and 6' Pup Joints (4.09 & 6.10)
11	1900	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
12		18.36	3.063	1.995	3 - 2 3/8 X 6' Pup Joints (6.13, 6.13, 6.10)
13	1878	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
14		6.2	3.063	1.995	2 3/8 X 2' and 4' Pup Joints (2.09, 4.11)
15	1870	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
16		36.53	3.063	1.995	1 Joint 2 3/8 Tubing (32.40) and 4' Pup Joint (4.13)
17	1830	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
18		32.2	3.063	1.995	1 Joint 2 3/8 Tubing
19	1797	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
20		32.19	3.063	1.995	1 Joint 2 3/8 Tubing
21	1761	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
22		10.33	3.063	1.995	2 3/8 X 6' and 4' Pup Joints (6.15, 4.18)
23	1749	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
24		36.33	3.063	1.995	1 Joint 2 3/8 Tubing (32.25) and 4' Pup Joint (4.08)
25	1708	3.81	3.080	1.870	2 3/8 X 1.87 "CMD" Sliding Sleeve
26		16.26	3.063	1.995	2 3/8 X 6', 4', & 6' Pup Joints (6.06, 4.20, 6.00)
27	1691	1.25	4.786	1.984	45B Model "C-1" Tandem Tension Packer
28		2.08	3.063	1.995	2 3/8 X 2' Pup Joint
29		0.67	3.668	1.995	2 7/8 Box X 2 3/8 Pin Change-over Sub
30		2	3.668	2.441	2 7/8 2' Pup Joint
31	1685	1.08	3.668	2.250	2 7/8 Standard Seating Nipple
32		1684.82	3.668	2.441	52 Joints 2 7/8 Tubing

**Run w/1.78 "RZG" Blanking Plug in "R" Nipple
Set 3.75' above Ground Level w/25,000# Tension**