

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400422842

Date Received:

07/24/2013

PluggingBond SuretyID

20090078

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Julie Webb Phone: (303)831-3933 Fax: ()

Email: julie.webb@pdce.com

7. Well Name: Gutttersen Well Number: 6U-443

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11226

## WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 6 Twp: 2N Rng: 63W Meridian: 6

Latitude: 40.174460 Longitude: -104.472510

Footage at Surface: 75 feet FNL/FSL 444 feet FEL/FWL  
 FNL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4836 13. County: WELD

## 14. GPS Data:

Date of Measurement: 10/16/2013 PDOP Reading: 1.6 Instrument Operator's Name: Thomas G. Carlson

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 734 FNL 526 FEL 500 FSL 520 FEL  
 Sec: 6 Twp: 2N Rng: 63W Sec: 6 Twp: 2N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5280 ft

18. Distance to nearest property line: 5280 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 459 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| CODELL                 | CODL           |                         | 160                           | GWA                                  |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T2N-R63W Section 6: E2

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 320

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF        | 12+1/4       | 9+5/8          | 36    | 0             | 875           | 830       | 875     | 0       |
| 1ST         | 8+3/4        | 7              | 26    | 0             | 7378          | 650       | 7378    | 500     |
| 1ST LINER   | 6+1/8        | 4+1/2          | 11.6  | 6058          | 11226         |           |         |         |

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 160 acres, E2E2 of Sec. 6 T2N R63W. Proposed spacing unit map and 30-day certificate is attached. Used the anti-collision report to find distance to the nearest well-Cuykendall 2-6.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Webb

Title: Regulatory Analyst Date: 7/24/2013 Email: julie.webb@pdce.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 10/9/2013

#### API NUMBER

05 123 38274 00

Permit Number: \_\_\_\_\_ Expiration Date: 10/8/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Description**

Operator must meet water well testing requirements per Rule 318A.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

**Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

**Attachment Check List**

| <b><u>Att Doc Num</u></b> | <b><u>Name</u></b>     |
|---------------------------|------------------------|
| 2167493                   | EXCEPTION LOC WAIVERS  |
| 400422842                 | FORM 2 SUBMITTED       |
| 400429586                 | PLAT                   |
| 400429587                 | DEVIATED DRILLING PLAN |
| 400429588                 | DIRECTIONAL DATA       |
| 400436097                 | PROPOSED SPACING UNIT  |
| 400454839                 | OFFSET WELL EVALUATION |
| 400454843                 | 30 DAY NOTICE LETTER   |
| 400454844                 | EXCEPTION LOC WAIVERS  |
| 400454845                 | EXCEPTION LOC REQUEST  |

Total Attach: 10 Files

**General Comments**

| <b><u>User Group</u></b> | <b><u>Comment</u></b>   | <b><u>Comment Date</u></b> |
|--------------------------|---|----------------------------|
| Permit                   | Attached 318A.c waiver as per opr. Final review complete.   | 10/7/2013<br>11:10:30 AM   |
| Permit                   | Requested signed 318Ac waiver from opr.   | 9/26/2013<br>11:07:34 AM   |
| Permit                   | Operator requested change in distance to the nearest building..... to 5280'.  | 8/14/2013<br>9:20:30 AM    |
| Engineer                 | Evaluated any existing wells within 1500' of proposed directional. All OK including: 123-11571, CUYKENDALL 2-6: PR, Isolation OK, annular fill x CBL@16 hrs ~830' up into surf csg. Requested Form 5 to update well file. | 8/8/2013<br>12:35:40 PM    |
| Permit                   | This form has passed completeness.  | 7/25/2013<br>9:34:20 AM    |

Total: 5 comment(s)

**Best Management Practices**

| <b><u>No</u></b> | <b><u>BMP/COA Type</u></b> | <b><u>Description</u></b> |
|------------------|----------------------------|---------------------------|
|                  |                            |                           |