

13 3/8" Surface Casing Cement



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 39451
LOCATION Oakley KS
FOREMAN Fuzzy
12114 Gable

FIELD TICKET & TREATMENT REPORT
CEMENT

Colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3-16-13		UPPER 14-S 1X	5	14S	44W	Cherokee
CUSTOMER Pronghorn			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 553" Production			405	Damon M		
			528	Jeremy S		
CITY	STATE	ZIP CODE				

JOB TYPE Surface HOLE SIZE 17 1/2 HOLE DEPTH 475' CASING SIZE & WEIGHT 133 1/8 - 54 1/2 #
CASING DEPTH 460' DRILL PIPE 4 1/2 TUBING _____ OTHER _____
SLURRY WEIGHT 14.7 SLURRY VOL 1.36 WATER gal/sk 6.5 CEMENT LEFT in CASING 30'
DISPLACEMENT 66.4 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting on well at #1. Rig up and circulate. Mix
425SKS Class 'A' 390cc 29 gal. Drop plug and displace
106 1/2 BBL and shut in. Cement did circulate approx
10 BBL to pit.

Thanks Fuzzy & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	1695 ⁰⁰	1695 ⁰⁰
5406	85	MILEAGE	5 ⁰⁰	425 ⁰⁰
5407A	20 ton	Tow mileage delivery	162	2839 ⁰⁰
1104S	425SKS	Class 'A' cement	1765	7501 ²⁵
1102	1199#	Calcium chloride	.89	1067 ¹¹
1118B	799#	Bentonite	.25	199 ⁷⁵
4436	1	133 1/8 wood cup plug	171 ⁰⁰	171 ⁰⁰
		Subtotal		13898 ¹¹
		less 1090		1398 ⁸¹
		Subtotal		12499 ³⁰
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION [Signature] TITLE MANAGING MEMBER DATE 3/16/13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 39366
LOCATION Oakley KS
FOREMAN Fuzz4

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

Colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-2-13	6378	UPRR 14-S 1X	S	14S	44W	Cherokee
CUSTOMER Pronghorn			cherokee wells w. also 3 1/4 in			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			463	Travis W		
			693	Tim W		
				Damon M - Trainee		
CITY	STATE	ZIP CODE				

JOB TYPE Production HOLE SIZE 7718 HOLE DEPTH 5631 CASING SIZE & WEIGHT 5 1/2 15.5 #
CASING DEPTH 5608 1/2 DRILL PIPE TUBING #32 + #73 OTHER PC
SLURRY WEIGHT 14.2 SLURRY VOL 1.42 WATER gal/sk CEMENT LEFT in CASING 42 1/4
DISPLACEMENT 132.4 DISPLACEMENT PSI MIX PSI RATE

REMARKS: Safety meeting on wildcat #1 Float equip Cont 1,2,3,31,72
Turbolizers 4,5,6,33,74 PCollars Top #32 + 73. Bag Ass bottom 32 + 73
Circ @ #70 = 30 min. Pick up and circulate 3 hrs. Pump 5 BBL water, 500 gal
mud flush, 5 BBL water. Mix 5 SKS RN, 5 SKS MN. Mix 130 SKS OWC
down 5 1/2 csg. Wash pump and lines. Drop plug and displace 132 1/4
BBL lost returns @ 116 BBL out gain back @ 122 BBL 500 #
maximum lost process. lost and gained returns intermittently
until 130 BBL had 200 # and climbing when plug landed @
1200 #. Float held

Thank Fuzz4 crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3650 ⁰⁰	3650 ⁰⁰
5406	85	MILEAGE	5 ⁰⁰	425 ⁰⁰
5407	6.6 Ton	Ton mileage Delivery	167	936 ⁸⁷
1126	140 SKS	OWC	22 ³⁵	3157 ⁰⁰
1144G	500 GAL	Mud Flush	1 ⁰⁰	500 ⁰⁰
4159	1	5 1/2 - AFU Float shoe (w)	413 ⁰⁰	413 ⁰⁰
4130	5	5 1/2 - Centralizers (w)	58 ⁰⁰	290 ⁰⁰
4136	5	5 1/2 - Turbolizers (F)	72 ⁰⁰	360 ⁰⁰
4104	2	5 1/2 - Bag Bits (w)	276 ⁰⁰	552 ⁰⁰
4285	2	5 1/2 - Port Collars (F)	2075 ⁰⁰	4150 ⁰⁰
4454	1	5 1/2 - Hatchdown Assy (F)	303 ⁰⁰	303 ⁰⁰
		subtotal		14736 ⁸⁷
		less 1090		14736 ⁸⁷
		subtotal		13263 ¹⁹
1111	100 #	SALT W/C	W/C	
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION [Signature] TITLE Manager DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.