



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER / 37942
LOCATION Oakley, KS
FOREMAN Kelly Gabel

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
7-15-13	4595	Nattie #1		6	145	44W	Cheyenne
CUSTOMER			Cheyenne Wells Rd 43 3N WIND	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS				399	Damon		
				529	Mike		
CITY							
STATE		ZIP CODE					

JOB TYPE <u>Surface</u>	HOLE SIZE <u>17 1/2</u>	HOLE DEPTH <u>470</u>	CASING SIZE & WEIGHT <u>13 3/8-46#</u>
CASING DEPTH <u>464</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>30'</u>
DISPLACEMENT <u>68</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety meeting, rigged up on wildcat drilling, hooked up to circulate, mixed 375 sacks com 3% cc 2% gel, released plug & displaced with 68 bbl water, shut in, washed out pump & lines rigged down.

Approx 7661 to pit

Thank You
Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	1725 ⁰⁰	1725 ⁰⁰
5406	85 mi	MILEAGE	5 ³⁵	446 ²⁵
11045	375 SKS	Class A cement	18 ⁵⁵	1391 ²⁵
1102	1057 #	calcium chloride	.94	993 ⁵⁸
1158B	205 #	Bentonite	.27	190 ³⁵
5407A	17.62	Ton mileage delivery	1 ⁷⁵	2621 ⁷²
4436	1	13 ³ / ₈ Wooden Plyg	179 ⁷⁵	179 ⁷⁵
				7547 ⁹⁰
				7547 ⁹⁰
				6793 ¹⁴
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

AUTHORIZTION

TITLE

DATE 1-11-73

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37989
LOCATION Okley, KS
FOREMAN Jerry Y (trainee)
Miles S

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-25-13	6378	Natic #1	6	145	44W	Cheyenne
CUSTOMER Pronghorn			Cheyenne Wells W-43			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon M		
			460	Travis		
CITY						
STATE						
ZIP CODE						

JOB TYPE long string HOLE SIZE 7 7/8 HOLE DEPTH 5623 CASING SIZE & WEIGHT 5 1/2 15.5
CASING DEPTH 5597 DRILL PIPE TUBING pc on 32 @ 43/8 OTHER pc on 75 @ 2504
SLURRY WEIGHT 12.5/14.2 SLURRY VOL WATER gal/sk CEMENT LEFT in CASING 10.36
DISPLACEMENT 132.97 DISPLACEMENT PSI MIX PSI RATE
REMARKS: Safety meeting a rig up on W. Heat #1 run float equipment centralizers on 1, 7, 31, 34, 74, 77
turbolizers on 2, 3, 4, 5, 6, 33, 76 baskets on bottom of 32, 75, p.c. on top of 32, 75 fill
pipe @ j⁺ 76 run pipe hook up to tree and pump ball thru run 5 bbl water, 500# mud flush, 5 bbl water mix
2 bbl in mh, 2 bbl in ch, mix 65 sks 60/40 88 gal 1/2 # flo seal lead and tail with 100 sks OWC
w/5 # Kol seal per sk 1/2 # flo seal per sk shut down clean pump & lines and release plug and displace with
130 1/2 bbl fresh water final float 750# plug landed @ 1300# released back & float held pressurized back
up to 500# and shut in for 15 min plug down @ 6:00 pm maint.
Thanks Jerry, Miles & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3400.00	3400.00
5406	85	MILEAGE	5.25	446.25
5407A	7.9	Ton mileage delivery	1.75	1175.13
1126	100 sks	OWC	23.70	2370.00
1110A	500 #	Kol Seal	.56	280.00
1107	87 #	flo seal	2.97	258.39
1131	75 sks	poz mix 60 /40	15.86	1189.50
1118B	516	bentonite	.27	206.40
1144G	500 gal	WFR mud flush	1.00	500.00
4159	1	5 1/2 AFU float shoe W	433.75	433.75
4454	1	5 1/2 latch down assy W	318.25	318.25
4130	6	5 1/2 centralizers W	61.00	366.00
4136	7	5 1/2 turbolizers W	75.75	530.25
4104	2	5 1/2 baskets W	290.00	580.00
4285	2	5 1/2 port collars I	2178.75	4357.50
		Subtotal		16411.42
		less 10% disc.	1,411.14	14,770.28
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION Josh Klesner TITLE Toolpusher DATE 7-25-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



FIELD TICKET & TREATMENT REPORT

FOREMAN Kelly Gabe

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-5-13		Nattie #1	6	145	246	Cheyenne
CUSTOMER Pronghorn			Cheyenne Wells			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon		
			528	mike		
CITY						
STATE		ZIP CODE				
		Winto				

JOB TYPE <u>Double Perforator</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER <u>DCS @ 4.375</u>
SLURRY WEIGHT <u>14 3/4 - 125</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>24 1/2 - 14</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on well, pressured tool to 1200#, tried to open bottom port collar & could not open, pulled tubing to 2502 to top port collar, pressured to 1200#, opened port collar & checked for blow, pumped 3c bbl water, mixed 250SKS 60/40 Po2 8% gel 1/4# flow & displaced with 14bbl water, shut tool & pressured to 1200#, ran 4 1/2" tubing & reversed out, washed out pump & lines, rigged down.

Thank You
Kelly & Crew

[illegible]

Ravin 3737

AUTHORIZATION [Signature] TITLE MANAGING MEMBER DATE 8-5-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.