



CONSOLIDATED
Oil Well Services, LLC

260861

TICKET NUMBER 38014LOCATION DAHEY KSFOREMAN Fuzzy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

Colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-24-	9160	Big Wagon #1	3	105	56W	Lincoln
CUSTOMER Weipking - Fullerton			Limen			
MAILING ADDRESS			S-56			
CITY			STATE			
ZIP CODE			TRUCK #			
			DRIVER			
			TRUCK #			
			DRIVER			

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>385</u>	CASING SIZE & WEIGHT <u>8 5/8</u>
CASING DEPTH <u>300</u>	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT <u>14.7</u>	SLURRY VOL <u>1.36</u>	WATER gal/sk <u>6.5</u>	CEMENT LEFT in CASING <u>20</u>
DISPLACEMENT <u>17.8</u>	DISPLACEMENT PSI	MIX PSI	RATE

REMARKS: Safety meeting on School Dalg - Rig up with 165 SKS
Class A 370cc 270cc Drop plug and displace 17 3/4 BBLs.
cement did circulate approx 5 BBLs to pit.

Thanks Fuzzy & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405	1	PUMP CHARGE	1150.00	1150.00
5406	1.00	MILEAGE	525	525.00
5407A	7.8	Tow mileage Delivery	175	1365.00
11045	165 SKS	Class A cement	18.52	3066.22
1102	465 #	Calcium chloride	.94	437.10
1108B	310 #	Bentonite	.27	83.70
4432	1	8 5/8 wood cap plug	100.25	100.25
4132	2	8 5/8 - Centralizers	86.00	172.00
4113	1	8 5/8 - Limit stop	52.00	52.00
		subtotal		6946.80
		less 1090		694.93
		subtotal		6251.87
		SALES TAX		268.96
		ESTIMATED TOTAL		6520.83

Pavin 9757

AUTHORIZATION Armando

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this for



CONSOLIDATED
Oil Well Services, LLC

Box 884, Chanute, KS 66720
0-431-9210 or 800-467-8676

261390

TICKET NUMBER **38040**
LOCATION Oakley, KS
FOREMAN Mike Shaw
Damen Miller trainee

FIELD TICKET & TREATMENT REPORT

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-15-13	9160	Big Wampum #1	2	105	54W	Lincoln
CUSTOMER <u>Wing King Fullerton</u>			Hugoco			
MAILING ADDRESS			SR			
CITY			STATE			
ZIP CODE			25			
			1 1/2 W			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			452 TIR	Doren D		
			560	M. H. P		

OB TYPE 5" Long Str. B HOLE SIZE 7 1/8" HOLE DEPTH 7412 CASING SIZE & WEIGHT 5 1/2" 17.4
CASING DEPTH 7491 DRILL PIPE TUBING OTHER
SLURRY WEIGHT 14.2 SLURRY VOL 1.42 WATER gal/sk CEMENT LEFT in CASING Net 16 4871.7
DISPLACEMENT 174 1/2 DISPLACEMENT PSI 800 MIX PSI 1500 psi RATE
REMARKS: Safety Meeting and rig up on Martin Drilling #25 Fluorquinone
turbolizers on Sats 2, 3, 4, 5, 6, 7, 8, 9, 10 Centralizer on Sats 62 + 64 Baskets
on Sats Bottom #2 10' down from collar on 63 Central top #63 @ 4871.75'
Run 100 Sats in Circulate 30 min Run rest casing to bottom Circulate
1 hr. Pump 5000 water Mud Flush 5000 Mix 1500 SPS Class H Cement
With 5" Kol Seal 100 Salt 20 gel down casing. Shut down released plug
cleared pump & line displaced 174 1/2 bbls water with 800 psi 1 ft plug
land and hold @ 1500 psi Mix 10 SPS R# 10 SPS MH

Thanks Mike & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	31.75 ⁰⁰	31.75 ⁰⁰
5406	100	MILEAGE	5.25	525 ⁰⁰
5407A	8.27 Tons	Ton Milled cement	1.75	1447.00
1115A	17 1/2 SPS	Class H Cement	16.75	2948.00
1111	880 #	Salt	1.50	440.00
1110A	880 #	Kol Seal	1.56	492.80
1118B	330 #	Brantite gel	1.27	89.10
11446	500 gal	Mud Flush	1.00	500.00
9104	2	5 1/2" Baskets	290.00	580.00
4130	2	5 1/2" Centralizers	61.00	122.00
4136	9	5 1/2" Turbolizers	75.75	681.75
4159	1	5 1/2" Flat Shoe	433.75	433.75
4285	1	5 1/2" Port collar	2178.75	2178.75
4454	1	5 1/2" latch down plug	318.25	318.25
			Subtotal	13931.40
			less 10% discount	1393.14
			Subtotal	12538.26
			SALES TAX	604.80
			ESTIMATED TOTAL	13143.06

Ravin 3737

AUTHORIZATION

Bryan Smith

TITLE CC-022

DATE 8/15/13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this for



FIELD TICKET & TREATMENT REPORT

CEMENT

TICKET NUMBER 38061
LOCATION OKLEY KS.
FOREMAN KELLY GIBBEL
ORT PAULSON M. TRAINING
CO.

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-19-13	9160	Big Wampum #1	23	185	56W	LINCOLN
CUSTOMER						
WHIPPING FULLERTON			LIMON			
MAILING ADDRESS			E 4026	TRUCK #	DRIVER	TRUCK #
			RD 5 W	456 F-118	DANE	
			W/N INTD	566	JACK	
CITY	STATE	ZIP CODE	RIVER	DJ		

JOB TYPE <u>PORT COLLAR</u>		HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 17#</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER _____	
SLURRY WEIGHT <u>12.5</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____	
DISPLACEMENT <u>27 BAR</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____	
REMARKS: <u>SAFETY MEETING RIG UP ON COLELL WELL SERV. RIG, RIG UP</u> <u>PRESSURE TOOL @ 1500 OPEN TOOL PUMPED 250 SKS 60/40 690 GEL</u> <u>1/4" FLO SEAL 2% CALCIUM DISPLACED W/ WATER 27 BAR PRESSURE UP</u> <u>TO 1500# RAN 5 JOINTS THAN REVERSED OUT WASHED UP. THAN</u> <u>RAN 40 BAR OF KCL RIGGED DOWN.</u>				

[illegible]

Bayin 3737

AUTHORIZTION

TITLE

DATE 8-19-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.