



FIELD TICKET & TREATMENT REPORT

37979

LOCATION

Oakley ks

FOREMAN

Walt Dinkel

CEMENT

Cold

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-15-13	9160	ma-state #3	24	10S	56W	Lincoln
CUSTOMER Wied King - Fullerton			Limon Cdo			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			456-7118	Jerry Yates		
			566	Daniel		
CITY	STATE	ZIP CODE				

JOB TYPE Surface HOLE SIZE 12 1/4" HOLE DEPTH 305' CASING SIZE & WEIGHT 8 5/8" - 20#

CASING DEPTH 300 DRILL PIPE _____ TUBING _____ OTHER _____

SLURRY WEIGHT 15.2 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 15'-20'

DISPLACEMENT 17.2 DISPLACEMENT PSI _____ MIX PSI _____ RATE 5 Bpm

REMARKS: Safety meeting. Pic up on School Dr. Girl casing on bottom.

mix 16.5 s/s conc. 3% cc - 2% gel. release Plu^- + Displace $17\frac{1}{4}$ TBV H_2O

shift in

Cement Dred Circ.

Thank You
Walt & crew

[illegible]

Rayin 3737

AUTHORIZTION

Ermano

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

TICKET NUMBER 38101
LOCATION Oakley Ks
FOREMAN Jerry Y
Walt D

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-30-13	9160	Ma State #3	24	10S	56W	Lincoln
CUSTOMER <u>Weipking Fullerton</u>						
MAILING ADDRESS <u>Hugo 5N Rd 26, 2 S, 1 1/2 W Ninto</u>						
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
			156	Jeremy R		
			160	Jack J		

JOB TYPE longstring HOLE SIZE 7 7/8 HOLE DEPTH 1068 CASING SIZE & WEIGHT 5 1/2 17#
CASING DEPTH 7383 DRILL PIPE TUBING OTHER P.C. top of 62 @ 4838
SLURRY WEIGHT 14.2 SLURRY VOL WATER gal/sk CEMENT LEFT in CASING 33.54'
DISPLACEMENT 170.52 DISPLACEMENT PSI MIX PSI RATE

REMARKS: Safety meeting & rig up on Martin 25, run float equ. turbolizers on 2, 3, 4, 5, 6, 7, 8, 9, centralizers on 6, 1, 2, 3, baskets on bottom of 2, 6, 2, port collar on top of 62 @ 4838 run 100 ft & circulate vis & 45 min rest hook up to rig & pump ball down
Pump 500 gal mud flash, mix 161 sks class H, 10% salt, 5# Kolseal, 2# bentonite
clear Pump & lines, release Plug & Displace 170 1/2 BBL @ 800# LIFT, 1 and 1/2
Plug @ 1300#, release Pressure, Float Head
10 sks in Milt
10 sks in R.H.

Thank You
Jerry-Walt & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	3,175.00	3,175.00
5406	100	MILEAGE	5.25	525.00
5407A	8.5	ten mileage deliver	1.75	1488.00
115A	181 sks	class H cement	16.75	3031.25
1111	948#	salt	.50	474.00
1110A	338 900#	Kolseal	.56	504.00
1118B	338#	Bentonite	.27	91.36
1144G	500 gal	WPR mud flash	1.00	500.00
4159	1	5 1/2 APU Float shoe w	433.75	433.75
4454	1	5 1/2 latchdownassy w	318.25	318.25
4130	2	5 1/2 centralizers w	61.00	122.00
4136	8	5 1/2 turbolizers w	75.75	606.00
4104	2	5 1/2 baskets w	290.00	580.00
4285	1	5 1/2 port collar I	2178.75	2178.75
		subtotal		14,027.76
		less 10% disc		1402.78
		subtotal		12,624.98
		SALES TAX		608.62
		ESTIMATED TOTAL		13233.60

Ravin 9737

AUTHORIZATION [Signature] TITLE cc-rep DATE _____
I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

