



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 44315  
LOCATION OKLEY, KS  
FOREMAN FUZZY  
DAMON M. TRAINING

# FIELD TICKET & TREATMENT REPORT

## CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-21-13	6378	HARLEY #2	5	14S	44W	CHEYENNE
CUSTOMER			TRUCK #			
Mailing Address			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE			TRUCK #			
			DRIVER			

JOB TYPE SURFACE HOLE SIZE 17 1/4 HOLE DEPTH 465 CASING SIZE & WEIGHT 13 3/8 48 #  
CASING DEPTH 457 DRILL PIPE TUBING OTHER  
SLURRY WEIGHT 14.8 SLURRY VOL WATER gal/sk CEMENT LEFT in CASING 30'  
DISPLACEMENT 67.8 BAR DISPLACEMENT PSI MIX PSI RATE

REMARKS: SAFETY MEETING RIG UP ON WILDCAT DRILLING COMPANY. HOOKED  
UP TO CIRCULATE, MIN 375 SKS. OF COMANON 3% CALCIUM 2% GEL.  
375 SKS  
DROP PLUG AND DISPLACE 67 BBLs WATER  
CEMENT DID CIRCULATE APPROX 20 PALS TOP  
Thanks Damon

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1150.00	1150.00
5406	85 mi	MILEAGE	5.25	446.25
5407A	17.6 ton	TON MILEAGE DELIVERY	1.75	2618.00
11045	375 SKS	CLASS A CEMENT	18.55	6956.25
1102	1058 #	CALCIUM CHLORIDE	.94	994.52
11188	705 #	BETONITE	.27	190.35
4436	1	13 3/8 WOODEN PLUG	179.75	179.75
		Subtotal		12535.12
		Less 10.90		12535.12
		Subtotal		11281.61
		SALES TAX		
		ESTIMATED TOTAL		

AUTHORIZATION Joh Klu TITLE Toolpusher DATE 8-21-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 38100  
LOCATION Oakley KS  
FOREMAN Jerry Y  
Fuzzy M

# FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
8-29-13	6378	Harley #2	5	14S	44W	Cherokee	
CUSTOMER	Pronghorn		Cheyenne Wells				
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER	
			463	Travis W			
			397	Daniel D			
CITY	STATE	ZIP CODE					
JOB TYPE	long string	HOLE SIZE	7 7/8	HOLE DEPTH	5545	CASING SIZE & WEIGHT	5 1/2, 15 1/2 #
CASING DEPTH	5549	DRILL PIPE		TUBING	PC 3 1/2 Top of j 31 @ 4214.20	OTHER	PC 2 3/4 Top of j 76 @ 2317.4
SLURRY WEIGHT	12.5/142	SLURRY VOL		WATER gal/sk		CEMENT LEFT in CASING	10.33'
DISPLACEMENT	131.63	DISPLACEMENT PSI		MIX PSI		RATE	

REMARKS: Saffy meeting & rig up on Wildcat #1 run float ega. centralizers on 2, 8, 34, 35, 36  
turbolizers on 3, 4, 5, 6, 7, 32, 33, baskets on top 30, 75, port collar on top of 31 @ 4214.20  
port collar on top of 76 @ 2317.42 hook up to rig mud tree break circulation & pump  
ball thru & circulate mud down to vis, hook up to pump truck, pump 5 bbl H<sub>2</sub>O, 500 gal mud flush  
5 H<sub>2</sub>O spacer, mix 5 sks in mh, 5 sks in rh, mix 50 sks 60/40 88 gel 1/4 # flo seal lead & 75 sks OWC  
w/ 5# Kol seal/bk & shut down release plug and wash pump & lines and displace w/ 31 1/2 bbl fresh water  
plug landed @ 1500# with a final lift of 950# released back 1/2 bbl & float held. Lost  
returns @ 75 bbl slowed to 2 bbl/min and got returns back @ 99 bbl out. Pressured back up to 500# & shut in  
for 30 min.

Thank you Jerry, Fuzzy & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401A	1	PUMP CHARGE	3400.00	3400.00
5106	85	MILEAGE	5.25	446.25
5407A	6.1	ton mileage delivery	1.72	907.37
1126	75 sks	OWC	23.70	1777.50
1110A	375 #	Kol seal	56	210.00
1131	60 sks	60/40 poz mix	15.36	951.60
1118B	413 #	gel	27	111.51
1107	15 #	flo seal	2.92	44.55
1144G	500 gal	w FR mud flush	1.00	500.00
4159	1	5 1/2 AFU float shoe w	433.75	433.75
4454	1	5 1/2 latchdown assy	318.25	318.25
4130	5	5 1/2 centralizers I	61.00	305.00
4136	7	5 1/2 turbolizers F	75.75	530.25
4104	2	5 1/2 baskets W	290.00	580.00
4285	2	5 1/2 port collars I SN 1300316/B 130829/T	2178.75	4357.50
		Subtotal		14875.55
		less 10% disc.		1487.55
		Subtotal		13,388.00
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION

*[Signature]*

TITLE

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

TICKET NUMBER 40031  
LOCATION Ogden, KS  
FOREMAN Mike Shaw

# FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																				
9-5-13	6378	Harley #2	5	14S	44W	Cherokee																				
CUSTOMER Poughorn			<table border="1"> <tr> <td>TRUCK #</td><td>DRIVER</td><td>TRUCK #</td><td>DRIVER</td></tr> <tr> <td>530TH8</td><td>Dano P</td><td></td><td></td></tr> <tr> <td>529TH9</td><td>Tim W</td><td></td><td></td></tr> <tr> <td></td><td></td><td></td><td></td></tr> <tr> <td></td><td></td><td></td><td></td></tr> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	530TH8	Dano P			529TH9	Tim W										
TRUCK #	DRIVER	TRUCK #					DRIVER																			
530TH8	Dano P																									
529TH9	Tim W																									
MAILING ADDRESS																										
CITY	STATE	ZIP CODE																								

JOB TYPE Port collar HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2" 15.5#  
 CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER 24/13 + 23/16  
 SLURRY WEIGHT 14.2/12.5 SLURRY VOL 1.42/1.9 WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 24/13 DISPLACEMENT PSI 1000/400 MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety Meeting and rig up on Eastern Cape Well Service. Test casing to 1000PSI; open tool pump 10 bbls water mix 100 SHS OWC displace 24 bbls water. Shut tool pressure casing to 1000PSI; hold reverse/out short way with 48 bbls water Vent 3 hrs. Pull up to to Port collar. Pressure casing to 1000PSI; open tool Pump 10 bbls water establish low mixed 250 SHS 60/40 Poz 88 gel 1/4 H Flo 28 Calcium displaced 12 3/4 bbls water Shut in test tool to 1000PSI; ran 3 in again reverse/out clean with 30 bbls water

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401B	1	PUMP CHARGE	1785 <sup>00</sup>	1785 <sup>00</sup>
5406	85 miles	MILEAGE	5.25	446.25
5407A	15.45 tons	Ton mileage delivery	1.75	2298.18
1126	100 SHS	OWC	23.70	2370.00
1131	250 SHS	60/40 poz	15.86	3965.00
1102	430 #	Calcium Chloride	1.94	404.20
1118B	1720 #	Bentinite gel	.27	464.40
1107	62 #	Flo Seal	2.97	184.14
			Subtotal	11917.17
			less 10% discount	1191.71
			Subtotal	10725.45
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

AUTHORIZATION [Signature]

TITLE \_\_\_\_\_

DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.