

**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

TICKET NUMBER 39103  
LOCATION Oakley, KS  
FOREMAN Walt Dinkal

## FIELD TICKET & TREATMENT REPORT CEMENT

C/c

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY	
10-28-12	9160	Makalo #11		29	103	55W	Lincoln	
CUSTOMER Wiepking-Fullerton				Limon 55 E. J	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS					399	Damon Miller		
					566	Tim Wareham		
CITY		STATE	ZIP CODE					

JOB TYPE	Surface	HOLE SIZE	12 1/4	HOLE DEPTH	304'	CASING SIZE & WEIGHT	8 5/8 - 23#
CASING DEPTH	300'	DRILL PIPE		TUBING		OTHER	
SLURRY WEIGHT	15.2	SLURRY VOL		WATER gal/sk		CEMENT LEFT in CASING	20' - 30'
DISPLACEMENT	18	DISPLACEMENT PSI		MIX PSI		RATE	5 BPM

REMARKS: Safety Meeting, rig up on Mur Fin #25, Circ casing on bottom  
mix 265 x/s com, 3%cc-2%gel, 1/4" Flo Seal, Release Plug + Displace  
18 BBL H<sub>2</sub>O @ 250#, Shut in

Cement Dicl Crs

Thank You  
Walt & crew

[illegible]

Ravin 3737

## AUTHORIZATION

TITLE DRUG SUP

DATE 10-28-2012

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 39116  
LOCATION Oakley, KS  
FOREMAN Kelly Gabe

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

# FIELD TICKET & TREATMENT REPORT

## CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-7-12	9160	Mahalo #11	29	10	55 <sup>00</sup>	Lincoln
CUSTOMER <u>Whie King Fullerton</u>						
MAILING ADDRESS						
CITY						
STATE						
ZIP CODE						
			TRUCK #	DRIVER	TRUCK #	DRIVER
			309	Damon		
			530T129	TRAUS Williams		

JOB TYPE Prod HOLE SIZE 7 7/8 HOLE DEPTH 7920 CASING SIZE & WEIGHT 5 1/2 17#  
CASING DEPTH 7910 DRILL PIPE  TUBING PCTOP #78 OTHER PC @ 4671'  
SLURRY WEIGHT 14 SLURRY VOL  WATER gal/sk  CEMENT LEFT in CASING 35' (shoe)  
DISPLACEMENT 182.7 DISPLACEMENT PSI  MIX PSI  RATE

REMARKS: Safety meeting, ran float equip on JTS turbochargers 2, 3, 4, 7  
11, 16, 17, 18, 19, 20, 21, 22 cent #77-79, PC top #78 ran 100 JTS  
& circulated for 1 1/2 hrs finished running pipe to bottom. Did not  
get circulation, pumped 5 bbl water, mud flush, 5 bbl water  
mixed 10 SKS R4 10 SKS mH, mixed 270 SKS classH 1070 salt.  
5# Kol-seal, 200 gal, cleared pumps & lines, released plug &  
displaced with 128 1/2 bbl water with lift pressure at  
1200#, plug landed at 1800#, released pressure, float held  
Rigged down float held.

*Thank you  
Kelly & crew*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4050 <sup>00</sup>	4050 <sup>00</sup>
5406	100	MILEAGE	5 <sup>00</sup>	500 <sup>00</sup>
1113A	290 SKS	ClassH cement	19 <sup>30</sup>	5597 <sup>00</sup>
1111	1377#	salt	.45	619 <sup>65</sup>
1110A	1450#	Kol-seal	.56	812 <sup>00</sup>
1115B	545#	Bentonite	.25	136 <sup>25</sup>
1107	73#	Flo-seal	283	205 <sup>86</sup>
11446	500 gal	mud flush	100	500 <sup>00</sup>
54107A	13.63	Ton mileage delivery	167	2277 <sup>00</sup>
4159	1	AFH Floatshoe (w)	4113 <sup>00</sup>	4113 <sup>00</sup>
41454	1	5 1/2 latchdown Assy w/plug	567 <sup>00</sup>	567 <sup>00</sup>
4136	12	5 1/2 turbochargers (w)	72 <sup>00</sup>	864 <sup>00</sup>
4130	2	5 1/2 centralizer (I)	58 <sup>00</sup>	116 <sup>00</sup>
4104	2	5 1/2 basket (w)	276 <sup>00</sup>	552 <sup>00</sup>
4285	1	5 1/2 Portcollar (I)	2075 <sup>00</sup>	2075 <sup>00</sup>
				19284.76
				Less 1092.28
				1928.48
				17356.28
			SALES TAX	874.55
			ESTIMATED	18230.83
			TOTAL	18230.83
			DATE	11-8-12

Ravin 3737 \*

2:00AM

AUTHORIZATION

*[Signature]*

TITLE CO Super

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

02110011



## FIELD TICKET & TREATMENT REPORT

TICKET NUMBER 39110  
LOCATION Oakley Jc  
FOREMAN Walt Dink

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-12-12	9160	Mahalo #11	29	10 <sup>s</sup>	55 <sup>w</sup>	Lindsey
CUSTOMER Whipking-Fulleston						
MAILING ADDRESS						
CITY			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon Miller		
			566	Mike Mounther		

JOB TYPE Port Collar HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT \_\_\_\_\_  
CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 7/8 - OTHER D.C 4671'  
SLURRY WEIGHT 12.5 SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
DISPLACEMENT 26. DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety Meeting, rig up Equipment Test Casing @ 1500#  
Held, mix 250 sts cam, 6 label, 2 1/2 cc 1/4" Fl-Seal, Displace 26 BB  
H2O @ 1200, shot Tool run 5 Jts Taking reverse out Clog  
↳ Test to 1500# Held

[illegible]

Rayin 3737

## AUTHORIZTION

**TITLE**

SALES TAX	326.99
ESTIMATED TOTAL	8110.96
DATE	12-12-12

**I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.**

7511521