

WELLBORE DIAGRAM

Directions: WCRs 72 @ 37, 1/2 mi W, 660' S, 660' E into

Bayswater E & P Eisenach #1

NWNE Sec 12-T6N-R66W
SHL: 660' FNL, 1980' FEL
BHL: 660' FNL, 1980' FEL
Weld County CO
05-123-11860

Updated
5/15/2013
B. Barony

G.L.= 4806
K.B.= 4819
13

8-5/8" 24# set at 351'
Cmt'd w/ 50 sx to Surf.

TOC: 6450'
CBL

<< >>

Codell 7230'-7244', 4 spf reperforated on 5/9/13

5/15/13: Re-Frac, 26,510 gal fr water, 133,014 gal zirc gel,
118,020 gal SLF, 249,040 lbs 30/50 sand

PBTD= 7,320'

4 1/2", 11.6# LTC 7322' (7-7/8" O.H.)

TD MD= 7,326'

Cmt'd w/ 250 sx

TD VD= 7,326'