

## WELLBORE DIAGRAM

### Bayswater E & P Booth 4-26

NWNE Sec 26-T7N-R65W  
SHL: 248' FNL, 2554' FEL  
BHL: 684' FNL, 634' FWL  
Weld County CO  
05-123-36084

Directions: 78 and 45, 1/8th north, south west into. Middle of 3 wells.

Updated  
6/21/2013  
RO

G.L.= 4893  
K.B.= 4909  
16

8-5/8" 24# set at 732'  
Cmt'd w/ 275 sx to Surf.

TOC: 1200'  
CBL

<< >>

Perforate Codell from 7635 to 7648, 4 spf, 6-18-13

PBTD= 7,708'  
TD MD= 7,792'  
TD VD= 7,372'

4 1/2" 11.6# LTC 7725.80' OH 7 7/8"  
Cmt'd w/ 890 sx