

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400474679

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

09/11/2013

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: AGGREGATE STATE

Well Number: 16N-16HZ

Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Lauren Kucera

Phone: (720)929-6107

Fax: (720)929-7107

Email: lauren.kucera@anadarko.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NESE Sec: 9 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.151930

Longitude: -104.776028

Footage at Surface: 2389 feet FNL/FSL FSL 910 feet FEL/FWL FEL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4925

County: WELD

GPS Data:

Date of Measurement: 05/30/2013 PDOP Reading: 1.9 Instrument Operator's Name: BART PFEIFER

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FSL 1840 FSL 424 FEL FEL 1 FSL 410 FEL
 Sec: 9 Twp: 2N Rng: 66W Sec: 16 Twp: 2N Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☒ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: applicant is owner

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Lease description:

CO-000011097-001

Township 1 North, Range 66 West, 6th P.M.

Section 4: Lot 2; S/2NW/4; N/2SW/4

Section 5: Lot 1; S/2NE/4

Township 2 North, Range 66 West, 6th P.M.

Section 9: S/2

Weld County, Colorado

Total Acres in Described Lease: 714 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1097 Feet

Building Unit: 1053 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 910 Feet

Above Ground Utility: 761 Feet

Railroad: 5280 Feet

Property Line: 215 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 85 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 799 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Unit configuration: 2N-66W-Sec. 9 E2SE; Sec. 10 W2SW; Sec. 15 W2W2; Sec. 16 E2E2; Sec. 21 NENE; Sec. 22 NWNW

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		560	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 14682 Feet

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

Other disposal description:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent at which point they will either be land applied or taken to a licensed, commercial disposal site; decided upon based off of laboratory analysis of fluids. Cuttings disposal: If the surface owner authorizes and if it is feasible for this location at the time of drilling, water-based cuttings will be disposed of onsite using bioremediation/solidification product.

If the surface owner does not authorize onsite disposal and/or it is not feasible for this location at the time of drilling, water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field.

Operator will run open hole logs into the surface casing on the first well drilled on this pad.

Kerr-McGee Oil & Gas Onshore LP ("KMG") respectfully requests the Director to waive Rule 318A.m for this well. KMG is the operator of the encroached upon wells.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Lauren Kucera

Title: Regulatory Analyst II Date: 9/11/2013 Email: DJRegulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 10/18/2013

Expiration Date: 10/17/2015

API NUMBER

05 123 38330 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.</p> <p>2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara and from 200' below to 200' above the Sussex. Verify coverage with cement bond log.</p> <p>3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.</p>
--	---

Best Management Practices

No BMP/COA Type

Description

1	Planning	The nearest building unit is located 1,053' away from this well.
2	Planning	604c.(2).Q. Guy Line Anchors: Should guy line anchors be left buried for future use, they shall be identified by a bright marker greater than four (4) feet high and no more than one (1) foot east of the guy line anchor.
3	Planning	604c.(2).S. Access Roads: KMG will utilize the lease access road from Weld County Road 31 for drilling operations and maintenance equipment. The road will be properly constructed and maintained to accommodate for local emergency vehicle access.
4	Planning	604c.(2).V. Development From Existing Well Pads: Drilling from an existing well pad was not feasible for the development of these wells; however, this well pad will be considered for future well locations.
5	Traffic control	604c.(2).D. Traffic Plan: If required by the local government, a traffic plan will be coordinated with the local jurisdiction prior to commencement of operations. Weld County Road 31 is paved and maintained by Weld County and will therefore not require dust mitigation.
6	General Housekeeping	604c.(2).O. Loadlines: All loadlines shall be bullplugged or capped.
7	General Housekeeping	604c.(2).P. Removal of Surface Trash: A commercial size trash bin for removing debris will be located on site. This bin will be for use by all parties affiliated with the operation.
8	Storm Water/Erosion Control	604c.(2).W. Site-specific Measures: KMG maintains a Stormwater Management Plan that assesses erosion control for every KMG operated location. This well pad will be added to this plan once construction begins. This plan is updated every fourteen (14) days and after any major weather event.
9	Material Handling and Spill Prevention	604c.(2).F. Leak Detection Plan: Automation technology will be utilized at this facility. This technology includes the use of fluid level monitoring for the tanks and produced water sumps, high-level shut offs, and electronic sensors to monitor the interstitial space of double-walled produced water sumps. All automation is monitored by Kerr-McGee's Integrated Operations Center (IOC,) which is manned 24 hours per day, 7 days per week.
10	Material Handling and Spill Prevention	604c.(2).N. Control of Fire Hazards: KMG and its contractors will employ best management practices during the drilling and production of its wells and facilities and will comply with appropriate COGCC rules concerning safety and fire. KMG will ensure that any material that might be deemed a fire hazard will be will remain no less than twenty-five (25) feet from the wellhead(s), tanks and separator(s).
11	Construction	604c.(2).E. Multiwell Pads: This 2A application is for a three-well pad. Use of this multi-well pad will reduce surface impact.
12	Construction	604c.(2).M. Fencing Requirements: The completed wellsites will be surrounded with a fence and gate with adequate lock to restrict access to authorized personnel only. KMG personnel will monitor the wellsites regularly upon completion of the wells. Authorized representatives and/or KMG personnel shall be on-site during drilling and completion operations.

13	Construction	604c.(2).R. Tank Specifications: Two 500 barrel steel tanks will be temporarily placed on-site for use of the pre-spud rig. One tank will store water and the other will store water based mud.
14	Noise mitigation	604c.(2).A. Noise: A sound mitigation barrier (hay bales) will be placed along the eastern side of the pad location to damper noise during drilling and completions to the nearby Weld County Road 31. Sound surveys have been conducted on each rig type, which are utilized to anticipate any additional noise mitigation if necessary.
15	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
16	Drilling/Completion Operations	<p>Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5.</p> <p>At the time of permitting, the operator has identified the following well(s) as being within close proximity of the proposed wells: MAYER STATE 16-16, AGGREGATE 9-9</p>
17	Drilling/Completion Operations	604c.(2).B. Closed Loop Drilling System: KMG will use a closed loop or "pitless" system for drilling and fluid management and will not construct a reserve pit.
18	Drilling/Completion Operations	604c.(2).H. BOPE: Our rigs at a minimum will have a double ram with blind and pipe ram; and annular preventer.
19	Drilling/Completion Operations	604c.(2).I. BOPE Testing for Drilling Operations: Upon initial rig-up, BOPE's will be tested at a minimum of every 30 days.
20	Drilling/Completion Operations	604c.(2).J. BOPE for Well Servicing Operations: Blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves will be used during any future servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using low-pressure air and high-pressure fluid.
21	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All mud pits contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gages are used on pits utilized for the surface rig.
22	Drilling/Completion Operations	604c.(2).L. Drill Stem Tests: No drill stem tests are planned and none will be performed without prior approval from the director.
23	Drilling/Completion Operations	604c.(2).C. Green Completions: KMG will install Vapor Recovery Unit(s) (VRU) to prevent uncontrolled venting of flash gas. Environmental Control Devices (ECD) will be used to control working and breathing vapor losses for oil and water tanks. Temporary above ground polyethylene water pipelines will deliver water to location operations from larger trunk lines to reduce truck traffic and minimize air pollution.
24	Final Reclamation	604c.(2).T. Well Site Cleared: The wellsite will be cleared of all non-essential equipment within ninety (90) days after all wells associated with the pad have been plugged and abandoned.
25	Final Reclamation	604c.(2).U. Identification of Plugged and Abandoned Wells: Pursuant to rule 319.a.(5)., once the well has been plugged and abandoned, KMG will identify the location of the wellbore with a permanent monument that will detail the well name and date of plugging.

Total: 25 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400474679	FORM 2 SUBMITTED
400474686	DEVIATED DRILLING PLAN
400474687	WELL LOCATION PLAT
400474688	PROPOSED SPACING UNIT
400474690	OTHER
400474897	OffsetWellEvaluations Data
400474899	DIRECTIONAL DATA
400474900	EXCEPTION LOC WAIVERS
400474902	EXCEPTION LOC REQUEST
400474907	WAIVERS

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Offset wells evaluated.	9/30/2013 11:29:41 AM
Permit	Centralized E&P Waste Management Facility ID is 149021 from 2A. Ready to pass pending public comment.	9/20/2013 2:32:59 PM
Permit	This form has passed completeness.	9/12/2013 1:05:12 PM

Total: 3 comment(s)