

**FORM**  
**5**  
Rev  
02/08

**State of Colorado**  
**Oil and Gas Conservation Commission**  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
400428243

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 8960 4. Contact Name: Olga Chikaloff  
 2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-1600  
 3. Address: 410 17TH STREET SUITE #1400 Fax: (720) 279-2331  
 City: DENVER State: CO Zip: 80202

5. API Number 05-123-37054-00 6. County: WELD  
 7. Well Name: Antelope Well Number: B-V-33HNB  
 8. Location: QtrQtr: SWNW Section: 33 Township: 5N Range: 62W Meridian: 6  
 Footage at surface: Distance: 1471 feet Direction: FNL Distance: 430 feet Direction: FWL  
 As Drilled Latitude: 40.359390 As Drilled Longitude: -104.336720

GPS Data:  
 Date of Measurement: 06/20/2013 PDOP Reading: 2.6 GPS Instrument Operator's Name: Wyatt Hall

\*\* If directional footage at Top of Prod. Zone Dist.: 1322 feet. Direction: FNL Dist.: 877 feet. Direction: FWL

Sec: 33 Twp: 5N Rng: 62W

\*\* If directional footage at Bottom Hole Dist.: 1308 feet. Direction: FNL Dist.: 472 feet. Direction: FEL

Sec: 33 Twp: 5N Rng: 62W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 05/06/2013 13. Date TD: 05/13/2013 14. Date Casing Set or D&A: 05/11/2013

15. Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 10716 TVD\*\* 6262 17 Plug Back Total Depth MD 10716 TVD\*\* 6262

18. Elevations GR 4579 KB 4591 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:  
CBL, MUD

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	485	420	0	485	CALC
1ST	8+3/4	7	26	0	6,800	742	150	6,800	CBL
1ST LINER	6+1/8	4+1/2	11.6	6613	10,708				VISU

### STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

#### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,448		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Olga Chikaloff

Title: Engineering Technician Date: \_\_\_\_\_ Email: ochikaloff@bonanzacrk.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400428536	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400428248	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400430942	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400430945	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400430946	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400452927	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400452930	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)