

BILL BARRETT CORPORATION

P & A of Surface Hole

Dixon Federal 12D-23-692

AFE # - 17016D

API#: 05-045-21113

Surface Hole Location:

1504' FNL, 366' FWL, Section 23, T6S-R92W
Garfield County, Colorado

NAD 83 Lat. & Long: 39.515730° N, 107.642419° W

Hole Depth: 822' MD

Spud Date: 3/31/2012

Tubular Info:

| Type | Size (in) | Weight (lbs/ft) | Grade | Top (ft) | Bottom (ft from GL) |
|-----------|--------------|--------------------|-------|-------------|------------------------|
| Conductor | 14 | 36.00 | J-55 | 0 | 62 |
| Surface | 9 5/8 | 36.00 | J-55 | 0 | 802.8 |

Surface Cement Info: See Attached Halliburton PJR

Plug and Abandonment Procedure

1. Move in and Rig up service rig on Dixon Federal 12D-23-692
2. Run in hole with 90' 2 7/8" tubing
3. Pump Cement Plug per Halliburton Recommendations
4. Cut off Wellhead at ground level.