

Aristocrat 32-9 2 05-123-09725- Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

Existing

KB: 4854
GL: 4848

8 5/8" Surf Csg Shoe @ 442

Base Fox Hills @ 854

Current TOC @ 3000

SX Top @ 4414

SX perms @ 4475-4538

5 1/2" Prod Csg @ 4618
TD @ 4620

Planned

30 sx of cement

Welded Cap
Surface plug 6'-100'
CIBP @ 100'

165 sx of cement (0.0238 bbl/Inft
PC, 7.875 "OH w/ 20%, 0.0636
bbl/Inft SC)

Cut csg @ 900
stub plug @ 1000-240

Balanced plug @ 4415-4210

25 sx of cement 0.0238
bbl/Inft)

CIBP @ 4415 w/ min 2sx

