



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 900098

Date <b>8-23-13</b>	Well Owner <b>BONANZA CREEK</b>	Well No. <b>F-J-36 HNR</b>	STATE <b>NORTH PLATTE</b>
County <b>WELD</b>	State <b>COLORADO</b>		
Charge to <b>BONANZA CREEK ENERGY, INC.</b>			
Address <b>410 17TH ST., SUITE 1500 (ENSIGN-128)</b>			
City, State, Zip <b>DENVER, COLORADO 80202</b>			
Type of Job	Depth	Ft. <b>446</b>	
<b>Surface</b>	<b>9 5/8" CSG-36#-13 1/2" HWC</b>	Bottom of Surface	Ft. <b>436</b>
Plug	Plug Landed @ <b>394</b>	Ft.	Time On <b>2345</b>
Production	Pipe Landed @ <b>436</b>	Ft.	Plug Down <b>0145</b>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat ✓	390	SKS		
Poz. Mix				
Calcium Chloride	3.0	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	80	Miles		
Fuel Surcharge	80	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Centralizers	5	
Disp. Rate	5 BPM	Cement Guide Shoe	1	
Slurry Vol.	1.18 Cu.Ft./Sk	Cement Basket		
Slurry Wt.	15.0-15.2 PPG	Baffle Plate	1	
Water/Cement	5.0 Gal/Sk	Box Thread Lock	1	
Water Temp.	70°F			
Total Slurry Vol.	81.9	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @	200	PSI
Pre-Flush W/	20	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	30.4	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

  

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		40			
1224		Bulk Truck		40			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered by JOE, JOSH, TUCKER

Received by \_\_\_\_\_

Customer or His Agent