



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**900066**

Date <b>7-2-13</b>	Well Owner <b>BONANZA CREEK</b>	Well No. <b>K-D-30HOB</b>	Lease <b>State Antelope</b>
County <b>Weld</b>	State <b>COLORADO</b>		
Charge to <b>BONANZA CREEK ENERGY, INC.</b>			
Address <b>410 17TH ST., SUITE 1500 (CADE 22)</b>			
City, State, Zip <b>DENVER, COLORADO 80202</b>			
Type of Job	Depth	Ft. <b>475</b>	
<u>Surface</u> <b>9 5/8" CSB-36" 13 1/2" Hole</b>	Bottom of Surface	Ft. <b>474</b>	
Plug	Plug Landed @ <b>432</b>	Ft.	Time On <b>0000</b>
Production	Pipe Landed @ <b>474</b>	Ft.	Plug Down <b>0330</b>

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat ✓	420	SKS
Poz. Mix		
Calcium Chloride <b>K-D-30HOB 6515-106</b>	3.0	%
Gel % <b>1.3125</b> Fio-Cete 1/4 # Per Sack <b>000114</b>		
Mileage Charge <b>7-2-13</b>	100	Miles
Fuel Surcharge <b>7/25</b>	100	Miles
Additional Cement		SKS
Mixing Rate <b>4 BPM</b>	Centralizers <b>5</b>	
Disp. Rate <b>5 BPM</b>	Cement Guide Shoe <b>1</b>	
Slurry Vol. <b>1.18 Cu.Ft./Sk</b>	Cement Basket	
Slurry Wt. <b>15.0-15.2 PPG</b>	Baffle Plate <b>1</b>	
Water/Cement <b>5.0 Gal/Sk</b>	Box Thread Lock <b>1</b>	
Water Temp. <b>77°F</b>		
Total Slurry Vol. <b>88.2</b>	BBLS Cement	
Landed Plug @ <b>800</b>	PSI/Final Lift @ <b>400</b>	PSI
Pre-Flush W/ <b>15</b>	BBLS H <sub>2</sub> O	Tax Reference Code
Displace W/ <b>33.3</b>	BBLS H <sub>2</sub> O	State <b>CO 2.9%</b>
Circulate <b>3</b>	BBLS Cement	
		Sub Total
		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1208</b>		Pump Truck		<b>50</b>			
<b>1214</b>		Bulk Truck		<b>50</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered by **Justin & Josh**

Received by **[Signature]**

Customer or His Agent