

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400511373

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: State of CO

Well Number: 1S-66-36-6457BH

Name of Operator: BARRETT CORPORATION* BILL

COGCC Operator Number: 10071

Address: 1099 18TH ST STE 2300

City: DENVER

State: CO

Zip: 80202

Contact Name: Venessa Langmacher

Phone: (303)312-8172

Fax: (303)291-0420

Email: vlangmacher@billbarrettcorp.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20040060

WELL LOCATION INFORMATION

QtrQtr: SWSW Sec: 36 Twp: 1S Rng: 66W Meridian: 6

Latitude: 39.916959

Longitude: -104.732459

Footage at Surface: 951 feet FNL/FSL FSL 295 feet FEL/FWL FWL

Field Name: THIRD CREEK

Field Number: 81800

Ground Elevation: 5227

County: ADAMS

GPS Data:

Date of Measurement: 09/18/2013 PDOP Reading: 6.0 Instrument Operator's Name: Jim Kalmon

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FSL 785 FSL 500 FWL 785 FSL 500 FEL FEL
 Sec: 36 Twp: 1S Rng: 66W Sec: 36 Twp: 1S Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.(check all that apply) ☒ is committed to an Oil and Gas Lease.☒ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1S-R66W Section 36: All

Total Acres in Described Lease: 640 Described Mineral Lease is: ☐ Fee ☒ State ☐ Federal ☐ Indian

Federal or State Lease # 68-5600S

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 500 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1021 Feet

Building Unit: 1242 Feet

High Occupancy Building Unit: 4236 Feet

Designated Outside Activity Area: 5082 Feet

Public Road: 272 Feet

Above Ground Utility: 254 Feet

Railroad: 5280 Feet

Property Line: 295 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 286 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 500 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| NIOBRARA | NBRR | 407-800 | 640 | All |

DRILLING PROGRAM

Proposed Total Measured Depth: 12189 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 286 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Mud and Cuttings will be hauled to Krier Spreadfield (430225).

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: 430225 or Document Number:

CASING PROGRAM

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| CONDUCTOR | 24 | 16 | 65 | 0 | 60 | 50 | 60 | 0 |
| SURF | 13+1/2 | 9+5/8 | 36 | 0 | 800 | 430 | 800 | 0 |
| 1ST | 8+3/4 | 7 | 26 | 0 | 7900 | 660 | 7900 | 600 |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.6 | 7200 | 12189 | | | |

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Venessa Langmacher

Title: Sr Permit Analyst Date: _____ Email: vlangmacher@billbarrettcorp.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type**Description**

| | |
|--|--|
| | |
|--|--|

Best Management Practices**No BMP/COA Type****Description**

| | |
|--|--|
| | |
|--|--|

Attachment Check List**Att Doc Num****Name**

| | |
|-----------|----------------------------|
| 400511395 | OffsetWellEvaluations Data |
| 400511396 | DIRECTIONAL DATA |
| 400511397 | EXCEPTION LOC REQUEST |
| 400511399 | EXCEPTION LOC WAIVERS |
| 400511400 | MINERAL LEASE MAP |
| 400511401 | DEVIATED DRILLING PLAN |
| 400511402 | WELL LOCATION PLAT |

Total Attach: 7 Files

General Comments**User Group****Comment****Comment Date**

| | | |
|--|--|--|
| | | |
|--|--|--|

Total: 0 comment(s)