

PDC Energy
Ankenney 28-1
SENE 28 6N 64W
Weld County, CO
Current Wellbore - NOT TO SCALE!!!
7/12/2013

API#: 05-123-13683

GL Elevation: 4677'

Surface Casing:
8 5/8" 24# @ 308' w/ 220 sks cmt.

First String
3.5" 10.3# @ 7085' w/ 250 sks cmt

Second String
0

Parkman/Sussex

Top of Cement:
6085'

Perforations	
Old:	Niobrara "A": 6600'-6818'
	Codell: 6894'-6910'
	0
	0
New:	0
	0
	0
	0

CIBP set @ 6535

Niobrara

Codell

PBTD:	6987'
Casing TD:	0

NOTES

Dump 2 sx cmt on top of CIBP @ 6535', cut casing at 5985', 50 sack stub plug @ 5985', 200 sack plug to cover Parkman/Sussex (3900'-4700'), 100 sacks half in half out of surface casing from 258'-358', 10 sacks @ surface