



**Pumping
Service Report**

9185802

| | | | |
|---|-----------------------------------|-------------------------------|-----------------------|
| Client Name Anadarko Petroleum Corporation | Well Name Camp 1-24 | Job Date November 01, 2013 | Call Sheet 1032332 |
| Client Representative Mr Rigo Macias | Location SE NE Sec 24:T3N:R67W | Job Type Abandonment Plugs | |

Well Profile

| | |
|--|----------|
| Well Type: | Oil |
| Maximum Treating Pressure (psi): | 3,000.00 |
| Predicted Bottom Hole Static Temperature (°F): | --- @ -- |
| Bottom Hole Circulating Temperature (°F): | --- @ -- |
| Bottom Hole Logged Temperature (°F): | --- @ -- |

Tubing

| Size (in) | Weight (lb/ft) | Grade | Collapse Pressure (psi) | Capacity (bbl) | I.D. (in) | O.D. (in) | Depth From (ft) | Depth To (ft) |
|--------------|-------------------|-------|----------------------------|-------------------|--------------|--------------|--------------------|------------------|
| 3.500 | 7.700 | J-55 | 5,970.000 | 68.170 | 3.068 | 4.250 | 0.000 | 7,456.000 |
| 2.063 | 3.250 | J-55 | 7,690.000 | 22.210 | 1.751 | 2.325 | 0.000 | 7,456.000 |

Products

Plug 1

From Depth (ft):

To Depth (ft):

Plug Type : N/A

Acids/Blends/Fluids :

Lead 1: 15 Sacks of Thermal 35, Density = 15.4 lb/gal, Volume Pumped = 4 (bbl)
Water Temperature(°F) = 60 , Bulk Temperature(°F) = 60 , Slurry Temperature(°F) = 60
+ 0.5 % of CFR,
+ 0.25 % of FMC

Fluid & Cement Data

Expected Cement Top: --

Wellbore Fluid

| Fluid Type | Viscosity (cP) | Density (lbs/gal) | Yield Point (psi) | Temperature (°F) | Recorded@ |
|------------|----------------|-------------------|-------------------|------------------|--------------------|
| Water | -- | 8.340 | -- | -- | Nov 01, 2013 13:40 |

Units & Personnel

Units

| Truck Unit No. | Main Type | Sub Type | Tractor Unit No. | Main Type | Sub Type | Time On Location | Time Off Location |
|----------------|-----------|-----------------|------------------|-----------|------------------|-------------------|-------------------|
| 449095 | TRAILER | Utility Trailer | 201191 | PICKUP | 1 Ton | 11/01/13 03:00 PM | 11/01/13 05:30 PM |
| 445052 | TRAILER | SCM Twin | 745052 | TRACTOR | Tandem - Tractor | 11/01/13 03:00 PM | 11/01/13 05:30 PM |
| 746502 | BODY JOB | Baby Bulker | | | | 11/01/13 03:00 PM | 11/01/13 05:30 PM |

Crew and Bonuses

| Employee | Start Shift | End Shift | Second Start Shift | Second End Shift |
|--------------------|---------------------|---------------------|--------------------|------------------|
| Hardwick, Waco | 11/01/2013 03:00 PM | 11/01/2013 05:30 PM | | |
| Hall, Andrew | 11/01/2013 03:00 PM | 11/01/2013 05:30 PM | | |
| Contreras, Bennie | 11/01/2013 03:00 PM | 11/01/2013 05:30 PM | | |
| Feigenbaum, Andrew | 11/01/2013 03:00 PM | 11/01/2013 05:30 PM | | |