



02419999

BEFORE THE OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

IN THE MATTER OF CHANGES TO THE RULES)	CAUSE NO. 1R
OF PRACTICE AND PROCEDURE OF THE OIL)	
& GAS CONSERVATION COMMISSION OF THE)	DOCKET NO. 1307-RM-01
STATE OF COLORADO)	
)	ORDER NO. 1R-118


REPORT OF THE COMMISISON

TO ALL INTERESTED PARTIES AND TO WHOM IT MAY CONCERN:

Pursuant to a hearing before the Oil and Gas Conservation Commission of the State of Colorado ("COGCC") on September 17, 2013, at COGCC offices, 1120 Lincoln Street, Denver, the Commission promulgated amendments to its Rules and Regulations as described in **Appendix A** (100 series rules for Sensitive Wildlife Habitat), **Appendix VII** (Restricted Surface Occupancy Area Maps), **Appendix VIII** (Sensitive Wildlife Habitat Maps), and Statement of Basis and Purpose, attached and made part of.

ENTERED THIS 7th day of October, 2013, as of September 17, 2013.

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

By 
Robert J. Frick, Secretary

Appendix A

(Changes to COGCC 100-series rules for Sensitive Wildlife Habitat)

SENSITIVE WILDLIFE HABITAT shall mean:

- mule deer critical winter range (being both mule deer winter concentration areas (that part of the winter range where densities are at least 200% of the surrounding winter range density during the same period used to define winter range in 5 out of 10 winters), and mule deer severe winter range (that part of the winter range where 90% of the individuals are located during the average 5 winters out of 10 from the first heavy snowfall to spring green-up) in Data Analysis Units with > 7 deer per square kilometer) (west of Interstate 25 and excluding Las Animas County);
- elk winter concentration areas (west of Interstate 25 and excluding Las Animas County);
- pronghorn antelope winter concentration areas (west of Interstate 25);
- bighorn sheep winter range;
- elk production areas (being that part of the overall range occupied by the females for calving) (west of Interstate 25 and excluding Las Animas County);
- Columbian sharp-tailed grouse and plains sharp-tailed grouse production areas (being an area that contains 80% of nesting and brood rearing habitat for any identified population);
- greater sage-grouse production areas (being an area that contains 80% of nesting and brood rearing habitat for any population identified in the Colorado Greater Sage-Grouse Conservation Plan (CDOW, 2008);
- Gunnison sage-grouse production areas (being an area that includes a 4 mile buffer on active lek sites),
- lesser prairie-chicken focal areas (being an area that includes core populations and habitat necessary for a viable population);
- black-footed ferret release areas;
- Bald Eagle nest sites and winter night roost sites; and
- Golden Eagle nest sites.


Maps showing and spatial data identifying the individual and combined extents of the above habitat areas shall be maintained by the Commission and made available on the Commission website, and copies of the maps shall be attached as Appendix VIII. The extent of sensitive wildlife habitat is subject to update on a periodic but no more frequent than biennial basis and may be modified only through the Commission's rulemaking procedures, as provided in Rule 529. Any modifications to sensitive wildlife habitat shall not affect Form 2As or Comprehensive Drilling Plans approved prior to the effective date of such changes.

**Colorado Oil & Gas Conservation Commission
Rules of Practice & Procedure**

Appendix VII:
Restricted Surface Occupancy Area Maps



GIS Unit



-  Gold Medal Streams (300 ft buffer)
-  Designated Cutthroat Trout Habitat (300ft buffer)


-  Raptor Active Nest Sites (Bald and Golden Eagles, Ferruginous Hawk, Osprey, N. Goshawk, Peregrine and Prairie Falcons)
-  Bighorn Sheep Production Areas

**Restricted Surface Occupancy
All Activities**



-  Lesser Prairie-Chicken Leks
-  Greater Sage-Grouse Leks (2008)
-  Gunnison Sage-Grouse Leks


-  Plains Sharp-Tailed Grouse Leks
-  Columbian Sharp-Tailed Grouse Leks



-  Designated Cutthroat Trout Habitat (300 ft buffer)
-  Gold Medal Waters (300 ft buffer)


Restricted Surface Occupancy

Designated Cutthroat Trout and Gold Medal Waters



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526


Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



-  Lesser Prairie-Chicken Leks
-  Greater Sage-Grouse Leks (2008)
-  Gunnison Sage-Grouse Leks

Restricted Surface Occupancy

Greater Sage-Grouse, Gunnison Sage-Grouse,
Lesser Prairie-Chicken Leks




This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
317 W. Prospect Road
Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.




GIS Unit




- Columbian Sharp-Tailed Grouse Leks
- Plains Sharp-Tailed Grouse Leks

Restricted Surface Occupancy Columbian and Plains Sharp-Tailed Grouse Leks



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
317 W. Prospect Road
Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



- Golden Eagle Active Nests
- Bald Eagle Active Nests
- Prairie Falcon Active Nests
- Osprey Active Nests
- Peregrine Falcon Active Nests
- Ferruginous Hawk Nest Sites
- Northern Goshawk Active Nests

Restricted Surface Occupancy Raptor Active Nest Sites




Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.

Colorado Oil & Gas Conservation Commission Rules of Practice & Procedure

Appendix VIII: Sensitive Wildlife Habitat Maps

These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as “no surface occupancy” areas.




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

Black-Footed Ferret Release Sites	Golden Eagle Nest Site	Sensitive Wildlife Habitat All Activities	Lesser Prairie-Chicken Focal Areas	Elk Production Areas
Bighorn Sheep Winter Range	Bald Eagle Active Nest Sites		Gunnison Sage-Grouse Production Areas	Elk Winter Concentration Areas
Mule Deer Critical Winter Range	Columbian Sharp-Tailed Grouse Production Areas	 <small>GIS Unit</small> 	Greater Sage-Grouse Production Areas (2008)	Bald Eagle Winter Roost Sites
Pronghorn Antelope Winter Concentration Areas	Plains Sharp-Tailed Grouse Production Areas			



GIS Unit




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

Sensitive Wildlife Habitat

Bighorn Sheep Winter Range

 Bighorn Sheep Winter Range




This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



GIS Unit




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

-  Columbian Sharp-Tailed Grouse Production Areas
-  Plains Sharp-Tailed Grouse Production Areas

Sensitive Wildlife Habitat

Columbian and Plains Sharp-Tailed Grouse Production Areas




This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



GIS Unit



These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

-  Elk Winter Concentration Areas
-  Elk Production Areas
-  Elk Production/Winter Concentration Areas


Sensitive Wildlife Habitat

Elk Production and Winter Concentration Areas



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

-  Greater Sage-Grouse Production Areas (2008)
-  Gunnison Sage-Grouse Production Areas


Sensitive Wildlife Habitat

Greater Sage-Grouse Production Areas
and Gunnison Sage-Grouse Production Areas



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
317 W. Prospect Road
Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

Sensitive Wildlife Habitat


Lesser Prairie-Chicken Focal Areas

 Lesser Prairie-Chicken Focal Areas



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

Sensitive Wildlife Habitat

Mule Deer Critical Winter Range

 Mule Deer Critical Winter Range




This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



GIS Unit




These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

Sensitive Wildlife Habitat

Pronghorn Winter Concentration Areas

 Pronghorn Winter Concentration Areas




This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.



GIS Unit



These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.


Sensitive Wildlife Habitat

Black-footed Ferret Release Areas

 Black-footed Ferret Release Areas


This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
 317 W. Prospect Road
 Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.






GIS Unit



These maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner. Mapped areas should not be construed as "no surface occupancy" areas.

-  Bald Eagle Winter Roost Sites
-  Bald Eagle Active Nests
-  Golden Eagle Active Nests

Sensitive Wildlife Habitat Bald and Golden Eagle Activities



This product is produced and distributed by:
Colorado Parks and Wildlife, GIS Unit
317 W. Prospect Road
Fort Collins, CO 80526

Information depicted hereon is for reference purposes only and is compiled from best available sources. Reasonable efforts have been made to ensure the accuracy of this map. Colorado Parks and Wildlife expressly disclaims responsibility for damages or liability that may arise from the use of this map.

**Final Statement of Basis, Specific Statutory Authority, and Purpose
New Rules and Amendments to Current Rules of the Colorado Oil and Gas
Conservation Commission, 2 CCR 404-1**

Cause No. 1R, Docket No. 1307-RM-01

Updates to Restricted Surface Occupancy Area and Sensitive Wildlife Habitat maps

On September 17, 2013, the Colorado Oil and Gas Conservation Commission (COGCC) amended the Restricted Surface Occupancy Area (RSO) and Sensitive Wildlife Habitat (SWH) maps, which are Appendix VII and VIII, respectively, to the Rules and Regulations and Rules of Practice and Procedure of the Colorado Oil and Gas Conservation Commission, 2 Code Colo. Regs., 404-1 (Commission Rules), and made conforming changes to the Commission Rule 100-Series definition of Sensitive Wildlife Habitat. This statement sets forth the basis, specific statutory authority, and purpose for the new and amended rules as required by the State Administrative Procedures Act, and is incorporated into the rules by reference. §§ 24-4-101; 103(4)(c), C.R.S.

In adopting the amended rules, the Commission relied on the entire administrative record for this rulemaking proceeding. The administrative record includes the proposed rules and recommended modifications and alternatives; public comment, written testimony, and exhibits; and public hearing testimony.

This rulemaking began on June 14, 2013, when Commission Staff filed a Notice of Rulemaking with the Colorado Secretary of State. Draft proposed rules were attached to the notice. On June 17, 2013, the Commission approved the Commission Staff's June 14, 2013 Notice of Rulemaking and formally directed COGCC Staff to proceed with the instant rulemaking.

COGCC Staff held stakeholder meetings regarding the proposed rules on June 26 and July 31, 2013. The stakeholder meetings were open to the public and were advertised on the Commission's website. Pursuant to §§ 24-4-102(14.5) and 103(2), C.R.S., Commission Staff specifically invited a diverse group of participants to the stakeholder meetings and encouraged all attendees to participate in the rulemaking hearing and comment on the effect of the proposed rules.

During the stakeholder meetings, COGCC Staff, along with representatives from Colorado Parks and Wildlife (CPW), provided an overview of the proposed rules and responded to audience questions. Upon the conclusion of these meetings, the consensus of stakeholders was that additional stakeholder meetings were unnecessary.

Statutory Authority

§ 34-60-105(1), C.R.S. (Commission has the power to make and enforce rules).

§ 34-60-128(3)(d), C.R.S. (Commission shall promulgate rules, in consultation with CPW, to establish standards for minimizing adverse impacts to wildlife resources affected by oil and gas operations).

Purpose

In order to administer the Colorado Oil and Gas Conservation Act, § 34-60-101, C.R.S. (Act), and Commission Rules in a way that minimizes adverse impacts to wildlife resources, the COGCC, in consultation with CPW, must identify and locate wildlife resources that could be impacted by oil and gas development. The most appropriate mechanism for identifying wildlife species and habitats is to require operators to review information already produced and maintained by CPW as part of its statewide wildlife management activities. The CPW has and maintains a statewide classification and mapping system that identifies RSOs and SWHs throughout Colorado. CPW routinely updates its classification and mapping system as it collects new data. The purpose of this rulemaking is to update the Commission's RSO and SWH maps with the best reasonably available scientific data to insure that consultations required under Commission Rule 306.c. are occurring in appropriate locations.

RSO and SWH maps trigger the consultation requirements of Commission Rule 306.c., which provides for consultation between the Commission, CPW, the surface owner and the operator seeking approval of a Commission Form 2A Oil and Gas Location Assessment for a proposed location in an RSO or SWH area. The purpose of consultation under Rule 306.c is to allow the Director of the COGCC to determine whether conditions of approval are necessary to "minimize adverse impacts" from the proposed oil and gas operations in the identified sensitive wildlife habitat or restricted surface occupancy area. See Commission Rule 1202.a. For purposes of Commission Rule 1202.a., "minimize adverse impacts" means, wherever reasonably practicable, to (i) avoid adverse impacts from oil and gas operations on wildlife resources, (ii) minimize the extent and severity of those impacts that cannot be avoided, (iii) mitigate the effects of unavoidable remaining impacts, and (iv) take into consideration cost-effectiveness and technical feasibility with regard to actions taken and decisions made to minimize adverse impacts to wildlife resources, consistent with the other provisions of the Act. *Id.* See also, § 34-60-128(2), C.R.S. ("The commission shall administer this article so as to minimize adverse impacts to wildlife resources affected by oil and gas operations."); § 34-60-103(5.5), C.R.S. (defining "minimize adverse impacts").

Amendments to Appendix VII (RSO map) and Appendix VIII (SWH map) of the Commission Rules

The RSO and SWH rules were first added to the Commission Rules during the Commission's comprehensive 2008 rulemaking and as a result of the passage of the Colorado Habitat Stewardship Act of 2007, House Bill 07-1298, codified at § 34-60-128, C.R.S. RSO maps are "subject to update on a periodic but no more frequent than annual basis and may be modified only through the Commission's rulemaking process, as provided in Rule 529." Commission Rule 100 Series definition of RSO. SWH maps are "subject to update on a periodic but no more frequent than biennial basis and may be modified only through the Commission's rulemaking procedures, as provided in Rule 529." Commission Rule 100 Series definition of SWH. The maps in effect prior to this rulemaking were promulgated in 2008 and had not been updated since. The purpose of this rulemaking is to update the Commission's RSO and SWH maps with the best reasonably available scientific data to insure that consultations required under Commission Rule 306.c. are occurring in appropriate locations.

The maps are based on data that CPW collects as part of several ongoing activities. First, the Species Activity Mapping (SAM) program is organized around annual meetings between the CPW Geographic Information Systems (GIS) unit, biologists and district wildlife managers. At these meetings, the GIS analysts update the various species activity areas for mapped species based on any observed changes since the last mapping session four years earlier. Since 2008, CPW has updated the SAM maps in all four CPW regions (NE, NW, SE, SW); the updated RSO and SWH maps incorporate these new data.

Second, CPW collects data on lek (strutting or booming grounds) activity for several grouse species every year. CPW also maintains a raptor database that tracks the location of raptor nests. The database is updated as CPW biologists and district wildlife managers identify new nests or monitor existing nests. Since 2008, CPW has collected new nest data annually and that information is included in new RSO and SWH maps.

Third, CPW proposed a change in the way buffers are mapped around Gunnison sage-grouse leks. Approximately 85% of Gunnison sage-grouse are known to nest within a 4 mile radius of active lek sites. The existing SWH map for Gunnison sage-grouse production areas was created by placing 4 mile buffers around lek sites and then clipping the buffers to include only the sage brush vegetation type. There have been a number of issues with these clipped buffers. This has been a particular problem in the satellite population areas outside the Gunnison basin as many of the sage brush areas occur in linear strips. CPW does not believe the current clipped buffers allow for adequate consultation to address direct and indirect disturbance to leks and adjacent nesting areas. Accordingly the 4 mile buffers are not clipped in the update to the Gunnison sage-grouse SWH production area map.

Amendments to Commission Rule 100 Series definitions

The Commission Rule 100 Series definition of Sensitive Wildlife Habitat specifies what constitutes sensitive wildlife habitat with reference to numerous identified species, including “mule deer critical winter range” and “greater sage-grouse and Gunnison sage-grouse production areas.” This rulemaking resulted in revisions to the species-specific definitions of Sensitive Wildlife Habitat as identified below.

Mule deer critical winter range

CPW and the Commission have identified an error in the 100 Series definition of mule deer critical winter range. Critical winter range includes only that portion of severe winter range occurring in Data Analysis Units with at least 7 deer per square kilometer; this criteria was omitted from the definition, even though the published map is correct. CPW suggested amending the definition so that it accurately reflects the existing map. The definitional change, by itself, will not cause a change in the number of mapped acres; instead, the definition will conform to the map.

Lesser prairie chicken focal areas

In November 2012, the United States Fish and Wildlife Service (USFS) initiated a process to consider whether the lesser prairie chicken (LEPC) should be listed as a threatened species under the Endangered Species Act of 1973, 16 U.S.C. § 1531 *et seq.* On April 1, 2013, the Lesser Prairie Chicken Working Group, in association with the Western Association of Fish and Wildlife Agencies, which includes CPW, submitted a range-wide conservation plan for the LEPC to the USFS (Conservation Plan). The purpose of the Conservation Plan is to develop a conservation strategy that ensures the improvement and long-term sustainability of the LEPC throughout its current or expanded range, thereby minimizing the likelihood the LEPC will be listed as a threatened or endangered species by the USFS.

The Commission Rule 100 Series definition of sensitive LEPC habitat has been expanded to conform to the Conservation Plan. Prior to this rulemaking, sensitive LEPC habitat was defined as LEPC “production areas (being an area that includes 80% of nesting and brood rearing habitat).” This formula created a SWH designation equal to a 1.5 mile radius around lek sites that were active from 1998-2008.

As a result of this rulemaking, sensitive LEPC habitat has been redefined as LEPC “focal areas (being an area that includes core populations and habitat necessary for a viable population).” This formula expands SWH designation to *potential* LEPC habitat in the State, whereas the prior definition was limited to *current* habitat. The “focal area” concept is a component of the

Conservation Plan and refers to those areas of greatest importance to the species, and focuses habitat enhancement, maintenance, and protection in such areas.

Redefining LEPC sensitive habitat to include focal areas results in an 86% increase in the total SWH acreage for this species (from 338,314 acres currently to 628,081 acres). The Commission emphasizes that SWH maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner to determine whether conditions of approval are necessary to “minimize adverse impacts,” § 34-60-103(5.5), C.R.S., from the proposed oil and gas operations in the identified sensitive wildlife habitat area. Sensitive Wildlife Habitat mapped areas do not depict areas in which oil and gas development is restricted or prohibited. The Commission recognizes the consultation process imposes certain transaction costs on operators, regardless of whether the Commission ultimately concludes mitigation measures are necessary or appropriate. However, the Commission concludes such costs are justified by the additional protections consultation and, where applicable, resulting site-specific mitigation measures afford the species. This cost–benefit analysis does not hold true if SWH maps are improperly interpreted or applied to restrict or prohibit oil and gas development within SWH areas, rather than trigger consultation. Consequently, the Commission emphasizes that the SWH maps should not be construed or applied to restrict or prohibit oil and gas development within Sensitive Wildlife Habitat areas.

Greater sage grouse priority habitat

During this rulemaking the Commission chose to defer any revision to the greater sage-grouse SWH definition and also chose to refrain from updating the greater sage-grouse RSO map with more current data.

Gunnison sage grouse production areas

Prior to this rulemaking, SWH determinations for both Gunnison sage grouse and greater sage-grouse were made by reference to “production areas” through one definition which combined both species. During this rulemaking, the Commission made changes to the Gunnison sage grouse SWH definition and chose to defer any revision to the greater sage-grouse SWH definition.

Gunnison sage grouse SWH is now defined as “Gunnison sage-grouse production areas (being an area that includes a 4 mile buffer on active lek sites).” The substance of the Commission Rule 100 Series definition of greater sage-grouse SWH remains as it did prior to this rulemaking and is as follows: “greater sage-grouse production areas (being an area that contains 80% of nesting and brood rearing habitat for any population identified in the Colorado Greater Sage-Grouse Conservation Plan (CDOW, 2008).”

The revision in the SWH definition for Gunnison sage grouse results in an overall increase of 64% in SWH acreage for the species (from 650,845 acres to 1,066,858 acres). The Commission reiterates that SWH maps are used solely to trigger consultation between CPW, COGCC, operators, and the surface owner to determine whether conditions of approval are necessary to “minimize adverse impacts,” § 34-60-103(5.5), C.R.S., from the proposed oil and gas operations in the identified sensitive wildlife habitat area. Sensitive Wildlife Habitat mapped areas do not depict areas in which oil and gas development is restricted or prohibited.