

FORM
6
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400516428			
Date Received: 11/21/2013			

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.
A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: <u>100322</u>	Contact Name: <u>Leah Perkins</u>
Name of Operator: <u>NOBLE ENERGY INC</u>	Phone: <u>(970) 304-5222</u>
Address: <u>1625 BROADWAY STE 2200</u>	Fax: <u>(970) 304-5099</u>
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>	Email: <u>lperkins@nobleenergyinc.com</u>

For "Intent" 24 hour notice required, Name: MONTOYA, JOHN Tel: (970) 3974124
COGCC contact: Email: john.montoya@state.co.us

API Number <u>05-123-18780-00</u>	Well Name: <u>UPV</u>	Well Number: <u>27-5G3</u>
Location: QtrQtr: <u>SWNW</u> Section: <u>27</u> Township: <u>6N</u> Range: <u>63W</u> Meridian: <u>6</u>	County: <u>WELD</u>	Federal, Indian or State Lease Number: <u>59278</u>
Field Name: <u>WATTENBERG</u>	Field Number: <u>90750</u>	

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.459311 Longitude: -104.430075

GPS Data:
Date of Measurement: 05/16/2008 PDOP Reading: 2.5 GPS Instrument Operator's Name: Paul Tappy

Reason for Abandonment: Dry Production for Sub-economic Mechanical Problems
 Other _____

Casing to be pulled: Yes No Estimated Depth: 5000

Fish in Hole: Yes No If yes, explain details below

Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below

Details: Holes in casing found. It is not economical to repair well.

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	6796	6816	08/01/2013	BRIDGE PLUG	6686

Total: 1 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	9+7/8	7	17	473	200	473	0	VISU
1ST	6+1/4	3+1/2	7.7	6,964	100	6,964	5,854	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6746 with 2 sacks cmt on top. CIPB #2: Depth _____ with _____ sacks cmt on top.
 CIBP #3: Depth _____ with _____ sacks cmt on top. CIPB #4: Depth _____ with _____ sacks cmt on top.
 CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 100 sks cmt from 5100 ft. to 4900 ft. Plug Type: STUB PLUG Plug Tagged:
 Set 50 sks cmt from 2500 ft. to 2400 ft. Plug Type: OPEN HOLE Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
(Cast Iron Cement Retainer Depth)
 Set 210 sacks half in. half out surface casing from 550 ft. to 0 ft. Plug Tagged:
 Set _____ sacks at surface
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No
 Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. of _____ inch casing Plugging Date: _____
 *Wireline Contractor: _____ *Cementing Contractor: _____
 Type of Cement and Additives Used: _____
 Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Stephanie Dionne
 Title: Base Production Tech Date: 11/21/2013 Email: sdionne@nobleenergyinc.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: HICKEY, MIKE Date: 11/29/2013

CONDITIONS OF APPROVAL, IF ANY: _____ Expiration Date: 5/28/2014

COA Type	Description
	1) Provide 24 hour notice of MIRU to John Montoya at 970 397-4124 or e-mail at john.montoya@state.co.us. 2) For 550' plug: if cement is not circulated to surface, shut-in, WOC 4 hours and tag plug – must be 423' or shallower. Leave at least 100' of cement in the wellbore for each plug. 3) Properly abandon flowlines as per Rule 1103.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400516428	FORM 6 INTENT SUBMITTED
400516450	WELLBORE DIAGRAM
400516452	PROPOSED PLUGGING PROCEDURE
400516454	WELLBORE DIAGRAM

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Old style comp. rept. #190877 sub. 5/95 meets form 5/5A requirements.	11/25/2013 9:35:47 AM

Total: 1 comment(s)