

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400497646

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

10/17/2013

Well Name: State of CO

Well Number: 1S-66-36-1724CH

Name of Operator: BARRETT CORPORATION* BILL

COGCC Operator Number: 10071

Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

Contact Name: Venessa Langmacher

Phone: (303)312-8172

Fax: (303)291-0420

Email: vlangmacher@billbarrettcorp.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20040060

WELL LOCATION INFORMATION

QtrQtr: SWNW Sec: 36 Twp: 1S Rng: 66W Meridian: 6

Latitude: 39.925154

Longitude: -104.732413

Footage at Surface: 1343 feet FNL/FSL FNL 299 feet FEL/FWL FWL

Field Name: THIRD CREEK

Field Number: 81800

Ground Elevation: 5180

County: ADAMS

GPS Data:

Date of Measurement: 09/13/2013 PDOP Reading: 6.0 Instrument Operator's Name: Jim Kalmon

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
1927 FNL 500 FWL 1927 FNL 500 FEL
Sec: 36 Twp: 1S Rng: 66W Sec: 36 Twp: 1S Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T1S-R66W, Section 36: All

Total Acres in Described Lease: 640 Described Mineral Lease is: ☐ Fee ☒ State ☐ Federal ☐ Indian

Federal or State Lease # 68-56005

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 500 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1044 Feet

Building Unit: 1599 Feet

High Occupancy Building Unit: 4253 Feet

Designated Outside Activity Area: 3202 Feet

Public Road: 270 Feet

Above Ground Utility: 256 Feet

Railroad: 5280 Feet

Property Line: 299 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 285 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 500 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-800	640	Sec. 36:All

DRILLING PROGRAM

Proposed Total Measured Depth: 12211 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 339 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Mud and Cuttings will be hauled to Krier Spreadfield (430225).

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: 430225 or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	1490	430	1490	0
1ST	8+3/4	7	26	0	8000	670	8000	600
1ST LINER	6+1/8	4+1/2	11.6	7200	12211			

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Venessa Langmacher _____

Title: Sr Permit Analyst _____


Date: 10/17/2013 _____

Email: vlangmacher@billbarrettcorp.co _____

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____



Director of COGCC

Date: 11/29/2013 _____

Expiration Date: 11/28/2015 _____

API NUMBER

05 001 09786 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type**Description**

	1) Note surface casing setting depth change from 800' to 1490'. Increase cement coverage accordingly. 2) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 3) Comply with Rule 317.i and provide cement coverage from end of 7" to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
	Operator acknowledges the proximity of the non-operated CHAMPLIN 117 AMOCO #1 (API # 001-06917) well. Operator assures that this offset will be remediated per the DJ Basin Horizontal Offset Policy (options 3) or operator will address this well with mitigation option 4. Operator will submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.
	Operator acknowledges the proximity of the (STATE A #1 API# 001-06757; STATE A #3 API # 001-06805; STATE A #4 API # 001-06810; STATE A #5 API # 001-06824; STATE A #6 API # 001-06834)wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.

Best Management Practices

No BMP/COA Type

Description

--	--	--

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: \\DorDonSterling\oFarmReports\policy_nto.rdl. Please

Attachment Check List

Att Doc Num

Name

400497646	FORM 2 SUBMITTED
400497666	DIRECTIONAL DATA
400497667	DEVIATED DRILLING PLAN
400497669	EXCEPTION LOC REQUEST
400497673	EXCEPTION LOC WAIVERS
400497904	OffsetWellEvaluations Data
400498438	WELL LOCATION PLAT

Total Attach: 7 Files

General Comments

User Group

Comment

Comment Date

Permit	Surface restoration bond verified by TK at State Land Board.	11/27/2013 2:26:55 PM
Permit	Oper. corrected dist. to nearest well permitted & penetrated.	11/21/2013 8:56:17 AM
Permit	Req'd correction to dist. from nearest well permitted & penetrated.	11/13/2013 1:21:17 PM
Permit	This form passes completeness.	10/18/2013 2:56:34 PM
Permit	Returned to draft: 1) Describe T & R in lease. 2) Wrong well loc. plat attached (1724 BH).	10/18/2013 10:01:28 AM

Total: 5 comment(s)