

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400400098

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

10/29/2013

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Tailholt FD

Well Number: 11-374HN

Name of Operator: GREAT WESTERN OPERATING COMPANY LLC

COGCC Operator Number: 10110

Address: 1801 BROADWAY #500

City: DENVER State: CO Zip: 80202

Contact Name: Shannon Hartnett

Phone: (303)398-0351

Fax: ()

Email: regulatorypermitting@gwogco.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090080

WELL LOCATION INFORMATION

QtrQtr: NWNW Sec: 11 Twp: 6N Rng: 67W Meridian: 6

Latitude: 40.508314

Longitude: -104.867919

Footage at Surface: 241 feet FNL/FSL FNL 607 feet FEL/FWL FWL

Field Name: Wattenberg

Field Number: 90750

Ground Elevation: 4876

County: WELD

GPS Data:

Date of Measurement: 09/17/2013 PDOP Reading: 1.9 Instrument Operator's Name: R. Kay

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL

 460 FNL 1595 FWL 470 FSL 1595 FWL
 Sec: 11 Twp: 6N Rng: 67W Sec: 11 Twp: 6N Rng: 67W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.
(check all that apply) ☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

See attached map

Total Acres in Described Lease: 289 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 460 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 467 Feet
Building Unit: 575 Feet
High Occupancy Building Unit: 3496 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 593 Feet
Above Ground Utility: 584 Feet
Railroad: 2872 Feet
Property Line: 241 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 09/06/2013

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 562 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

W/2 Sec 11 T6NR67W

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-830	320	W/2

DRILLING PROGRAM

Proposed Total Measured Depth: 12101 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 562 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Land application

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

Land application

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	40	61	40	0
SURF	13+1/2	9+5/8	36	0	1025	426	1025	0
1ST	8+3/4	7	23	0	7657	699	7657	725
2ND	6+1/8	4+1/2	11.6	6897	12101			

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments: Onsite tank battery location already approved. Location ID = 431642
Location ID 433845 pad already approved and built
Casing 2nd string: uncemented liner with packers and ports

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 433845

Is this application being submitted with an Oil and Gas Location Assessment application? No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Shannon Hartnett

Title: Reg. Compl. Spec. Date: 10/29/2013 Email: regulatorypermitting@gwogco.c

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 12/7/2013
Expiration Date: 12/06/2015

API NUMBER

05 123 38579 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type**Description**

- | | |
|--|---|
| | <ol style="list-style-type: none">1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.2) Comply with Rule 317.i and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well. |
|--|---|

Best Management Practices

No	BMP/COA Type	Description
1	Planning	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed well path with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottom hole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
2	Community Outreach and Notification	Great Western is aware of the Conditional Use Grant process with the Town of Severance and will comply with such process and COA's in addition to the granting of the COGCC permit.
3	General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly and promptly.
4	Noise mitigation	Noise levels will be maintained at levels not to exceed COGCC specifications currently in existence, measured at a point 350' from the noise source, or as defined by current COGCC regulations. Where possible, drilling rig engine exhaust will be vented away from occupied buildings. Light sources will likewise be directed downwards, and away from occupied structures where possible. No special noise mitigation efforts should be required at this site. Once the drilling and completion rigs leave the site, there will be no permanently installed lighting on site.
5	Drilling/Completion Operations	Great Western will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.

Total: 5 comment(s)

Data retrieval failed for the subreport 'IntPolicy_MTO' located at: \\DorDanSterling\cFarmReports\policy_mto.rdl. Please

Attachment Check List

Att Doc Num	Name
2167550	EXCEPTION LOC REQUEST
2167551	PROPOSED SPACING UNIT
400400098	FORM 2 SUBMITTED
400503926	DIRECTIONAL DATA
400503927	DEVIATED DRILLING PLAN
400503928	PLAT
400503929	PROPOSED SPACING UNIT
400503930	EXCEPTION LOC WAIVERS
400503931	EXCEPTION LOC REQUEST
400503932	SURFACE AGRMT/SURETY
400503934	MINERAL LEASE MAP
400512106	DIRECTIONAL DATA

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review complete.	12/4/2013 2:49:37 PM
Permit	Attached corrected Proposed Spacing Unit, Exception Loc Request, Corrected Spacing, Removed 318A.c Exception, as per opr. Ready to pass pending public comment 11/20/13.	11/13/2013 11:01:26 AM
Permit	Exception location waiver is incorrect. Opr notified and new one requested. This area was spaced by GWOG in July for 407-830 NB-CD 320 6 HZ wells in W2. This is one of the six.	11/4/2013 11:45:43 AM
Permit	Passed completeness.	10/30/2013 1:29:30 PM
Permit	Operator requested correction to the MTD in the Drilling & Waste Plans tab.	10/30/2013 1:28:21 PM
Permit	Requested review of measured TD in the Drilling & Waste Plans tab as it doesn't match the casing and Deviated Drilling plan. Rig is on location and drilling at this time.	10/30/2013 5:47:03 AM

Total: 6 comment(s)