

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400523013

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Kathleen Mills
Phone: (720) 587-2226
Fax: (303) 228-4286

5. API Number 05-123-37194-00
6. County: WELD
7. Well Name: JENKINS
Well Number: B11-79-1HCM
8. Location: QtrQtr: NWSW Section: 11 Township: 5N Range: 64W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 08/31/2013 End Date: 08/31/2013 Date of First Production this formation: 11/13/2013

Perforations Top: 7253 Bottom: 14057 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

FRAC'D W/5982883 GAL SILVERSTIM AND SLICK WATER AND 7293941# OTTAWA SAND

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 142450 Max pressure during treatment (psi): 7870

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.77

Total acid used in treatment (bbl): Number of staged intervals: 32

Recycled water used in treatment (bbl): 7844 Flowback volume recovered (bbl): 8822

Fresh water used in treatment (bbl): 134606 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 7293941 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 11/17/2013 Hours: 24 Bbl oil: 379 Mcf Gas: 853 Bbl H2O: 171

Calculated 24 hour rate: Bbl oil: 379 Mcf Gas: 853 Bbl H2O: 171 GOR: 2251

Test Method: FLOWING Casing PSI: 2140 Tubing PSI: 1430 Choke Size: 20/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1122 API Gravity Oil: 38

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6821 Tbg setting date: 10/31/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kathleen Mills

Title: Regulatory Analyst

Date: _____

Email kmills@nobleenergyinc.com

:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
--------------------	-------------

--	--

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>
-------------------	----------------

Comment Date

--	--	--

Total: 0 comment(s)