

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400524314

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Eileen Roberts
Phone: (303) 2284330
Fax: (303) 2284286

5. API Number 05-123-36660-00
6. County: WELD
7. Well Name: TIMBRO
Well Number: LC13-77-1HNX
8. Location: QtrQtr: NENW Section: 24 Township: 9N Range: 59W Meridian: 6
9. Field Name: WILDCAT Field Code: 99999

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 07/01/2013 End Date: 07/01/2013 Date of First Production this formation: 07/25/2013

Perforations Top: 6497 Bottom: 10207 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 2219377 gals of Silverstim and Slick Water with 3064040#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 52842 Max pressure during treatment (psi): 4465

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.82

Total acid used in treatment (bbl): 0 Number of staged intervals: 20

Recycled water used in treatment (bbl): 3104 Flowback volume recovered (bbl): 208

Fresh water used in treatment (bbl): 49738 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 3064040 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/30/2013 Hours: 24 Bbl oil: 78 Mcf Gas: 374 Bbl H2O: 246

Calculated 24 hour rate: Bbl oil: 78 Mcf Gas: 374 Bbl H2O: 246 GOR: 4794

Test Method: FLOWING Casing PSI: 836 Tubing PSI: 258 Choke Size: 20/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1354 API Gravity Oil: 38

Tubing Size: 2 + 7/8 Tubing Setting Depth: 6277 Tbg setting date: 07/22/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Eileen Roberts _____

Title: Regulatory Specialist _____

Date: _____

Email: eroberts@nobleenergyinc.com _____

:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)