

FORM
2
Rev
08/13

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
400489308

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Date Received:

TYPE OF WELL OIL GAS COALBED OTHER CO2
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Refiling
Sidetrack

Well Name: CNE Well Number: 4
Name of Operator: KINDER MORGAN CO2 CO LP COGCC Operator Number: 46685
Address: 17801 HWY 491
City: CORTEZ State: CO Zip: 81321
Contact Name: PAUL BELANGER Phone: (970)882-2464 Fax: (970)882-5520
Email: PAUL_BELANGER@KINDERMORGAN.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20110027

WELL LOCATION INFORMATION

QtrQtr: t40 Sec: 1 Twp: 38N Rng: 19W Meridian: N
Latitude: 37.580750 Longitude: -108.893390

Footage at Surface: 2794 feet FNL/FSL FNL 2384 feet FEL/FWL FEL

Field Name: MCELMO Field Number: 53674

Ground Elevation: 6845 County: MONTEZUMA

GPS Data:
Date of Measurement: 09/26/2013 PDOP Reading: 1.8 Instrument Operator's Name: R J CAFFEY

If well is Directional Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL 2794 FNL 2384 FEL FEL 698 FSL 2376 FEL
Bottom Hole: FNL/FSL FEL/FWL
Sec: 1 Twp: 38N Rng: 19W Sec: 1 Twp: 38N Rng: 19W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is:
(check all that apply) is the mineral owner beneath the location.
 is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Bond

Surface damage assurance if no agreement is in place: Blanket Surface Surety ID: 20080051

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

1st lease: section 1 38N 19W: TRACT 37, LOTS 5,6,11 AND 12; sectin 35 39N19W E/2 - 480 ac
 2nd lease: section 1 38N 19W; SE 1/4 aka tract 40 - 160 ac
 combination of both 620 ac

Total Acres in Described Lease: 640 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 273 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2292 Feet
 Building Unit: 2292 Feet
 High Occupancy Building Unit: 5280 Feet
 Designated Outside Activity Area: 5280 Feet
 Public Road: 2401 Feet
 Above Ground Utility: 2656 Feet
 Railroad: 5280 Feet
 Property Line: 118 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
 - Enter 5280 for distance greater than 1 mile.
 - Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
 - Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
 - Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
 - Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 5280 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): McElmo Dome Unit Number: 047653X

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
LEADVILLE	LDVLL			

DRILLING PROGRAM

Proposed Total Measured Depth: 10397 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 5280 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule N/A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

NO SALT OR H2S expected in horizontal wellbore having been cased off uphole of this borehole.
DEWATER IN CLOSED LOOP SYSTEM; ANY Water after recycle is disposed of in our Class 1 disposal well. Solids to go to Montezuma County Land Fill.

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	65	0	80	100	80	0
SURF	14+3/4	10+3/4	40.5	0	3000		3000	0
1ST	9+1/2	7+5/8	29.7&33.7	0	8350		8350	0
OPEN HOLE	4+3/4		0	8350				8350

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number 318.b.

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

THIS APD IS FOR THE HORIZONTAL BOREHOLE; SEE 400489306 FOR THE ASSOCIATED PILOT.
There are no water wells located within a .5 mile radius of the CNE-4 Limit of Disturbance. A Form 4 will be filed accordingly.

Two separate Surface Use Agreements are being developed for both property owners (Brad E. White & Pamela K. and John A. Kuenzler) impacted by the construction of CO2 well, CNE-4. Please see Rule 318.b Variance Request for further information.

NO SALT OR H2S expected in horizontal wellbore having been cased off uphole of this borehole

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: PAUL BELANGER

Title: REGULATORY CONTRACTOR Date: _____ Email: PAUL_BELANGER@KINDER

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

<u>COA Type</u>	<u>Description</u>

Best Management Practices

No BMP/COA Type

Description

<u>No BMP/COA Type</u>	<u>Description</u>
1 Planning	A Kinder Morgan Fire Mitigation Plan is currently on file with the Montezuma County Planning Office. Any material not in use that might constitute a fire hazard will be removed a minimum of 25 feet from the wellhead, tanks and separator. Any electrical installations inside the bermed area will comply with API RP 500 classifications and comply with the current national electrical code as adopted by the State of Colorado.

2	Traffic control	<p>A Road Use Plan, which addresses traffic concerns specific to the CNE-4, is currently on file with Montezuma County. The traffic plan was produced after consulting with the county Road and Bridge Supervisor.</p> <p>All access roads are fully compliant with local county road standards. Access roads are composed of compacted gravel. In an effort to mitigate dust, magnesium-chloride applications to the road surface are performed at the request of Montezuma County.</p>
3	General Housekeeping	<p>Erosion control barriers, namely fiber wattles, will be placed at the edge of disturbance where necessary. Care will be taken to avoid disturbance outside of the project area unless it is deemed necessary for equipment stability and fire safety.</p> <p>On-site trash dumpsters are emptied regularly by the local waste management company.</p> <p>Steel ranch fencing will be placed around the well head after the well is drilled. Once the well is tied in, the fencing will be removed. The proposed well location will be drilled using a closed loop system and will therefore not use open pits. During drilling and completion operations, safety officers are present on location to ensure that livestock, wildlife, and unauthorized personnel do not enter the location. Following completion, the only items present on the well pad are the well head and aboveground pipeline junction. Additionally, there is no active grazing near the proposed location.</p>
4	Storm Water/Erosion Control	<p>Diversion ditches will be implemented to divert run-on and run-off around the well pad. Compacted earthen berms will also be utilized to control stormwater run-on and run-off.</p> <p>Tackifier will be added to the stored topsoil piles and all slopes to prevent erosion. Stockpiled soils will have slopes not greater than 3:1.</p> <p>Stormwater BMPs will be maintained/amended by Kinder Morgan as site conditions change throughout the construction and reclamation process.</p>
5	Material Handling and Spill Prevention	<p>The use of a closed-loop drilling system will reduce the amount of waste produced and water used during drilling operations. Solid cuttings will be disposed of at a licensed disposal facility.</p> <p>Recycled water will be disposed of in a Class I disposal well.</p> <p>Sufficiently impervious containment devices will be constructed around any condensate and produced water tanks. The containment devices will be sufficiently impervious to contain any spilled or released material. All containment devices will be inspected at regular intervals and maintained in good condition.</p> <p>All loadlines are capped.</p> <p>Tanks are designed to meet all API 650 guidelines.</p>
6	Construction	<p>All equipment will be stored within the right-of-way (ROW) area of disturbance. Top soil will be removed to create a level pad for drilling and access road (ROW: 50').</p> <p>Vegetation that does not need to be removed will be avoided during construction and removed vegetation will be cut near ground level, leaving the root system intact except where permanent facilities, roads, or ROWs require the complete removal of vegetation.</p>
7	Noise mitigation	<p>During normal operations, the well will remain within COGCC regulations for noise. However, during the construction phase of the project, this standard may be exceeded occasionally.</p>
8	Emissions mitigation	<p>Non-flammable CO₂ will be produced from the Leadville formation and thus green completion per rule 805 (3) does not apply.</p> <p>All CO₂ wells are equipped with a CO₂ leak detection monitor during drilling.</p>

9	Final Reclamation	<p>Blowout preventer equipment (BOPE) complies with COGCC equipment regulations.</p> <p>Mineral Management certification or Director approved training for blowout prevention has been conducted for at least one person at the well site during drilling operations.</p> <p>Kinder Morgan conducts a BOPE test and files a 24 hour notice (Form 42) at the initial rig-up time, after each casing emplacement, and/or every 30 days.</p> <p>KM standard operating protocol includes a check list for well-site clearance activities when a well is transferred from the Drilling Department to the Operations Department.</p> <p>Adequate blowout prevention equipment is used on all well servicing operations.</p> <p>Backup stabbing valves are used on well servicing operations during reverse circulation and are pressure tested before each well servicing operation using both low-pressure air and high-pressure fluid.</p> <p>No pits are present at the well site.</p>
10	Interim Reclamation	Surface roughening, surface contouring, seeding, and weed control will be employed to facilitate vegetation reestablishment. Tackifier will be added to reclaimed areas.
11	Final Reclamation	All disturbed areas that are not necessary for operational procedures will be restored to at least 80 percent of pre-disturbance vegetative cover.

Total: 11 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400525515	DRILLING PLAN
400525517	DEVIATED DRILLING PLAN
400525526	DIRECTIONAL DATA
400525528	PLAT
400525529	OIL & GAS LEASE
400525530	OIL & GAS LEASE

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)