



API# 0512323043				
Well: Strear 13-10				
Equipment	Specs	Depth	Capacity (bbl/ft)	Capacity ft ³ /ft
Surface Casing	8 5/8" 24#	900	0.0637	0.3576
Production	4 1/2" 11.6#	7710	0.0155	0.0873
Tubing Extension	N/A	N/A	N/A	N/A
Sx/ Sh Casing Hole size	9"		0.0787	0.4418
NB/CD Casing Hole size	12"		0.1399	0.7854

Cement Calculations				
Section	Volume	Cement Sacks	approximate	
S/C hole	71.52	46.75		Top Plug
P/C annular hole	180.25	117.81		
P/C hole	8.73	5.71		
Total Top Plug	260.50	170.26	200	

Sx/ Sh				SX/ SH Plug
In pipe	68.79	59.82	60	
Total			65	

NB/CD Annular	N/A	N/A		NB/CD Plug
NB/CD Csg.	34.92	25.30	25	
Total			30	

Cement Yield	1.53	1.15	1.71	1.38
	Top Plug	SX/SH	NB/Cd Sque	NB/Cd in pipe