

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-PFISTER 3-18

Project: COLORADO-WELD-NAD83-UTM13

Site: HSR-PFISTER 3-18

Rig Name No: KEY 104/104

Event: ABANDONMENT

Start Date: 11/16/2013

End Date: 12/2/2013

Spud Date: 3/18/1993

Active Datum: RKB @4,860.99usft (above Mean Sea Level)

UWI: NE/NW/0/3/N/67/W/18/0/0/6/0/N/865.00/W/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	11/16/2013		RU SLICKLINE, FISH TOOLS, TAG @ ', RUN GYRO, MIRU KEY 104
2	11/18/2013		KILL WELL, NU BOP, RU FLOOR & TONGS, TOO, RU WIRELINE, SET 4-1/2" CIBP @ 6760', LOG WELL FROM 5900'-3500', RD WIRELINE, SWI, DRAIN UP, SDFN
3	11/19/2013		TIH, LD EXTRA TBG, EOT @ 6750', RU CEMENTERS, PUMP 30SX OF 15.4# CLASS G CEMENT, PU HOLE, ROLL HOLE CLEAN @ 4655', PUMP 65SX OF 15.6# CLASS G CEMENT, PU HOLE, ROLL HOLE W/ MUD @ 3700, TOO, LD TBG, EOT @ 1600', SWI, DRAIN UP, SDFN
4	11/20/2013		TOO, LD TBG, RU WIRELINE, CUT CSG @ 860', ROLL HOLE, ND BOP, UNLAND CSG, NU SPOOL & BOP, LD CSG, TIH, EOT @ 955', RU CEMENTERS, PUMP 185SX OF 14.2# TYPE 3 CEMENT, PU HOLE, ROLL HOLE CLEAN @ 130', LD TBG, SWI, DRAIN UP, SDFN
5	11/21/2013		ND BOP & FLANGE, RU WIRELINE, TAG TOC @ 360', SET 8-5/8" CIBP @ 100', TEST CIBP TO 1000PSI - HELD, RDMO KEY 104
6	12/02/2013		Crew travel, Safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 91'. Filled casing stub with 40 bags 5000# cement. Capped casing w metal plate containing well info. Backfilled.
7	12/02/2013		P&A'd OFFLINE. NB/CD.