

THE ROBERT GERRITY COMPANY
DAILY COMPLETION REPORT

WELL NAME: Lucci-BC B01-14
LOCATION: SE SW Sec. 1-T5N-R64W
Weld County, Colorado
OPERATOR: The Robert Gerrity Company

6/09/89 (Per Wendall Jamison) MIRU Great Guns. Ran CBL and CCL logs. Estimated top of cement at 6240'. Bond 90% at 6090 - 6650, poor bond (25% with one 10' streak of 90% bond) at 6650 - 6750, 90% at 6790' - 6810', 70% at 6810' - 6880'.

6/15/89 MIRU Western. Pressure tested casing to 6500 psi.


7/11/89 MIRU H & R. Perforated Codell: 6736', 6737', 6738', 6739', 6740', 6742', 6744', 6746', 6748' with 9-.44" shots. Niobrara: 6623', 6635', 6648', 6558', 6560', 6562', 6570', 6430', 6455' with 9-.44" shots.

7/13/89 MIRU Western to frac Codell-Niobrara formation down 3-1/2" 9,3# casing using 67,000 gal. cross-linked frac along with 200,000# 20/40. Rate 26 bpm (avg), 4900 psi (avg), 6500 psi (max). Max concentration 5 ppg. Pumped 500 gal 15% HCl acid and 1,000 gal. KCl spacer ahead of frac. Flushed with 800 gal KCl flush.

Note: Scheduled job was 73,500 gal. cross-linked frac fluid and 250,000# 20/40.

(Notes per Frank Gambardella). Start acid 4 bpm 5400 psi. Start space 13 bpm 5500 psi. Shutdown to take ISDP - 3200 psi - slight bleedoff. Start pad 15 bpm 6000 psi - pressure decrease to 4600 psi. Increase rate to 25 bpm 5000 psi. Start 2 ppg sand 25.5 bpm 5900 psi. 2 ppg sand hit 25.5 bpm 4900 psi. Start 4 ppg 260 bpm 4650 psi. 4 ppg sand hit 26 bpm 4600 psi. Start 5 ppg sand 27 bpm 4800 psi. 5 ppg sand hit 27 bpm 4800 psi. Slight pressure increase 3000 gallons after 5 ppg sand hit to 5100 psi. Sharp pressure rise 11000 gallons after 5 ppg sand hit to 5700-5900 psi. Stayed on 5 ppg sand instead of 6 ppg sand and had sharp pressure rise as went to flush 23 bpm 5600 psi. Flushed 800 gallons out of 2460 gallons. Pumped 67000 crosslinked fluid and 200,000# 20/40 sand. Left 7000# sand in casing.

7/14/89 CP 2300 psi on 8/64 choke. Opened at 4:00 PM.



FIELD TICKET # 4740

DATE 5-6-05

15581 Hwy 14 • P.O. Box 447 • Sterling, CO 80751
970-526-1084

TRUCK # T-4

SERVICE *Perf*

CUSTOMER

LEASE

WELL#

ADDRESS

COUNTY

STATE

CITY

LEGAL DESCRIPTION

SECTION

TOWNSHIP

RANGE

STATE

ZIP

ORDERED BY

TRUCK OPERATOR

WITNESSED BY

FOOTAGE
SERVICED

SERVICE PERFORMED

UNIT
PRICE

TOTAL

1 ¹¹ / ₁₆	Sinker Box, LCL	TAG SAND PLUG	596 ²⁵ / ₁₀₀	300 ²⁰ / ₁₀₀
---------------------------------	-----------------	---------------	------------------------------------	------------------------------------

6558-6578	2 $\frac{1}{8}$ "	6VN SLINGER	120 SHOTS	10 SHOTS @	1300 $\frac{24}{2}$
-----------	-------------------	-------------	-----------	------------	---------------------

6452-6472	2 $\frac{1}{8}$ " GUN SLINGER	120 SHOTS	230 SHOTS/25'	5750 ⁰⁰
-----------	-------------------------------	-----------	---------------	--------------------

Second Gun Run	300 ⁰⁰
----------------	-------------------

	6 SPFT
	60° PHASE
	.27" E.H.
	27.51" PEN
	6.5 gram charge

Chick	L-1	P 1.5
-------	-----	-------

Kyle	2-1	P1.5
------	-----	------

TOTAL CHARGES	7650 ⁰⁰
---------------	--------------------

I CERTIFY THAT THE ABOVE MATERIALS OR SERVICES HAVE BEEN RECEIVED,
THAT THE BASIS FOR CHARGES IS CORRECTLY STATED, AND THAT I AM AUTHORIZED
TO SIGN THIS MEMORANDUM AS THE AGENT OF OWNER OR THE CONTRACTOR.

AGENT OF OWNER
OR CONTRACTOR

CHARGES ARE SUBJECT TO
CORRECTIONS BY OUR INVOICING
DEPARTMENT IN ACCORDANCE WITH
LATEST PRICE SCHEDULES AND THE
ADDITION OF APPLICABLE STATE AND
LOCAL SALES/USE TAX IF NOT LISTED
ABOVE

WHITE - ACCOUNTING
GOLD - CUSTOMER
CANARY - INVOICE
PINK - FIELD