

Furrow #1

660' FSL, 660' FWL, (SW SW), Sec. 18, T5N. R61W, 6th P.M.

Lat 40.395477, Long -104.259345 (from footages)

Weld County, Colorado

API # 05-123-05181

Spud date 4/27/1956

P & A 5/11/1956

4532' KB

4542' GL

10 3/4", 32#, set @ 106',
cemented to surface w/ 150 sx.

Spot 200 sx cmt plug, 400' to Surface

Note: No plugging records available
on the COGCC website.

400'

2700'

Spot 200 sx cmt plug, 2700-3200'

3200'

Parkman 3214'

Niobrara 5914'

Ft Hayes 6208'

8 3/4" TD 6597'

D Sand 6602'

J Sand 6667'

7 7/8" TD 6816'

TD = 6816'

5/10/1956

OH Plug?, no record

All Depths KB

Updated December 10, 2013 srw