

**SCHAAL DRILLING, CO.**  
**46881 Hwy 24 BURLINGTON, CO. 80807**  
**719-346-8032**  
**FIELD REPORT**  
**SURFACE CASING, DRILLING AND CEMENTING**

DRILLING DATE 12-27-11

WELL NAME & LEASE # On-The-Brink 843-3-14

MOVE IN, RIG UP, DIG PITS ETC. DATE 12-26-11 TIME 5:15 AM **PM**

SPUD TIME 6:30 **AM** PM SHALE DEPTH 330 TIME 12:15 AM **PM**

HOLE DIA. 9 7/8 FROM **0** TO 467 +12 479 TD TIME 2:15 AM **PM**

CIRCULATE, TOO, MEASURED 461.85 FT CASING 473.85 KB FT SET DEPTH

11 JOINTS 7 0D #/FT **17** 20 23 16.04 @ Amherst yard

PUMP 105 SAC CEMENT 762 GALLONS DISP. CIRC. 4 BBL TO PIT

PLUG DOWN TIME 3:45 AM **PM** DATE 12-27-11

CEMENT LEFT IN CSG. 30

CENTRALIZER 3

CENTRALIZER SET@ 1-2 5-6 10-11

TYPE : PORTLAND CEMENT I/II ASTM C 150

CEMENT COST \$ 1672.52

Cement 14.5#s

CR 36 & Hwy 23 3/4 E on CR 36 N 356ft

ELEVATION 3667

+12KB 3679

**PIPE TALLY**

1. 41.95 11. 41.70

2. 41.75 12.

3. 41.95 13.

4. 42.30 14.

5. 42.15 15.

6. 41.65 16.

7. 41.95 17.

8. 42.15 18.

9. 42.35

10. 41.95 **Total**  
461.85