

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400530239

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☒

ZONE TYPE SINGLE ZONE ☐ MULTIPLE ZONES ☒ COMMINGLE ZONES ☒

Sidetrack ☐

Date Received:

Well Name: Piceance Creek Unit

Well Number: T78X-12G7

Name of Operator: XTO ENERGY INC

COGCC Operator Number: 100264

Address: 382 CR 3100

City: AZTEC

State: NM

Zip: 87410

Contact Name: Cherylene Charley

Phone: (505)333-3190

Fax: (505)333-3284

Email: cherylene_charley@xtoenergy.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: _____

WELL LOCATION INFORMATION

QtrQtr: SESE Sec: 12 Twp: 2S Rng: 97W Meridian: 6

Latitude: 39.884935

Longitude: -108.222550

Footage at Surface: 300 feet FNL/FSL FSL 1067 feet FEL/FWL FEL

Field Name: PICEANCE CREEK

Field Number: 68800

Ground Elevation: 7263

County: RIO BLANCO

GPS Data:

Date of Measurement: 11/06/2009 PDOP Reading: 1.7 Instrument Operator's Name: D. GARDINER

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:	FNL/FSL	FEL/FWL	Bottom Hole:	FNL/FSL	FEL/FWL
214	FSL	272	214	FSL	272
Sec: 7	Twp: 2S	Rng: 96W	Sec: 7	Twp: 2S	Rng: 96W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☐ State ☒ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

*See previously approved APD dated 4/1/10.

Total Acres in Described Lease: 2247 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COD-035705

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 97 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet

Building Unit: 5280 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 680 Feet

Above Ground Utility: 589 Feet

Railroad: 5280 Feet

Property Line: 5280 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 933 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 5280 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): Piceance Creek Unit Number: COC-47666A

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MESAVERDE	MVRD			
OHIO CREEK	OHCRK			
WASATCH	WSTC			

DRILLING PROGRAM

Proposed Total Measured Depth: 14900 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 934 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? Yes

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: ONSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Cuttings trench

Other Disposal Description:

If drill cuttings/fluids contain >1% diesel net weight, cuttings will be transported via tanker truck to state approved disposal site.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	line pipe	0	120	96	120	0
SURF	14+3/4	10+3/4	45.5	0	4200	1360	4200	0
1ST	9+7/8	7	26	0	9650	720	9650	3700
2ND	6+1/8	4+1/2	15.1	0	14100	270	14100	6800

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments This is a re-file of a previously approved APD, which expired on 5/24/12. I certify that there have been no changes on land use, lease description and drilling program. The well pad and pits have not been constructed. There will be no additional surface disturbance. The location does not require a variance from any of the rules listed in Rule 306.d.(1). (A).(ii). The location is not within a wildlife Restricted Surface Occupancy Area.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cherylene Charley

Title: Sr. Permitting Tech Date: _____ Email: cherylene_charley@xtoenergy.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05 103 11722 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

No BMP/COA Type

Description

1	Drilling/Completion Operations	<p>These devices may include, but are not limited to:</p> <ul style="list-style-type: none">• Culvert• Rip Rap• Drainage ditch• Wattles• Erosion control blankets• Temporary seeding <p>Additional documentation is located in the Stormwater Management Plan for this well pad.</p>
---	--------------------------------	---

Total: 1 comment(s)

Attachment Check List

Att Doc Num Name

--	--

Total Attach: 0 Files

General Comments

User Group Comment

Comment Date

--	--	--

Total: 0 comment(s)